

# SUMMARY OF QUANTITIES

CONTINUAL NO. 64931				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HR	ROCKISLAND	139	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(IL 5)				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN			BRIDGE X271-2A 80% FED 20% STATE
				IL 92/IL 5 J000 80% FED 20% STATE	IL 84 J000 80% FED 20% STATE		
20200100	EARTH EXCAVATION	CU YD	2855	325	2530		
20400800	FURNISHED EXCAVATION	CU YD	385	385			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,910			1,910	
28000400	PERIMETER EROSION BARRIER	FOOT	1000	1000			
28000500	INLET AND PIPE PROTECTION	EACH	5	5			
28100107	STONE RIPRAP, CLASS A4	SQ YD	223	217	6		
28100208	STONE RIPRAP, CLASS A4 (SPECIAL)	TON	2792	2792			
28200200	FILTER FABRIC	SQ YD	223	217	6		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	9370	5651	3719		
31200100	STABILIZED SUB-BASE 4"	SQ YD	2638		2638		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	238	238			
40600990	TEMPORARY RAMP	SQ YD	40	40			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	266	124	142		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50	TON	56	56			
40603340	HOT MIX ASPHALT SURFACE COURSE, MIX 'D' N 70	TON	466	466			
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	2143	2143			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	684	684			
42001200	PAVEMENT FABRIC	SQ YD	4780	4780			
42001300	PROTECTIVE COAT	SQ YD	3693	1287	2406		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PPC)	SQ YD	2404	2404			
42100100	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	2406		2406		
42100700	PAVEMENT REINFORCEMENT 8"	SQ YD	2406		2406		
44000100	PAVEMENT REMOVAL	SQ YD	4523	2145	2378		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4426	4426			
44000300	CURB REMOVAL	FOOT	160	160			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1799	1104	695		
44001900	CONCRETE BARRIER REMOVAL	FOOT	201	201			
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	18875	13880	4995		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1418	488	930		
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	171	171			
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	44	44			
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	189	189			
44213200	SAW CUTS	FOOT	1335	1335			

• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY

PLOT DATE = Thu Sep 28 14:28:18 2007  
FILE NAME = c:\projects\2006293\486289pl.dgn  
PLOT SCALE = 50.0000 / IN.  
USER NAME = ccs11193