

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	SHEETS	NO.
#595	SHBR	ROCKISLAND	139	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*(IL 5)

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	IL 92/IL 5 J000 80% FED 20% STATE	IL 84 J000 80% FED 20% STATE	BRIDGE X271-2A 80% FED 20% STATE	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2186	1044	1142		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1	
50157300	PROTECTIVE SHIELD	SQ YD	3474	2243		1231	
50200100	STRUCTURE EXCAVATION	CU YD	2396			2396	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	103.5			103.5	
50300225	CONCRETE STRUCTURES	CU YD	1,699.2			1,699.2	
50300255	CONCRETE SUPERSTRUCTURES	CU YD	391.8			391.8	
50300260	BRIDGE DECK GROOVING	SQ YD	1375			1375	
50300300	PROTECTIVE COAT	SQ YD	1559			1559	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1	
50500505	STUD SHEAR CONNECTORS	EACH	5631			5631	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	649,380			649,380	
50800515	BAR SPLICERS	EACH	892			892	
51100100	SLOPE WALL 4 INCH	SQ YD	120			120	
51500100	NAME PLATES	EACH	1			1	
51603000	DRILLED SHAFT IN SOIL	CU YD	250			250	
51604000	DRILLED SHAFT IN ROCK	CU YD	435			435	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	214			214	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28			28	
52100520	ANCHOR BOLTS, 1"	EACH	56			56	
54200217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	33	33			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	28			28	
5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	49	49			
54215547	METAL END SECTIONS 12"	EACH	2	2			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1			
55037800	STORM SEWERS TO BE CLEANED 12"	FOOT	164	164			
55100500	STORM SEWER REMOVAL 12"	FOOT	63	63			
58700300	CONCRETE SEALER	SQ FT	8165			8165	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	941			941	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3		3		
60107600	PIPE UNDERDRAINS 4"	FOOT	1234		1234		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	288			288	
60238630	INLETS, TYPE A, WITH SPECIAL FRAME, OPEN LID	EACH	2	2			
60247160	DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	5	5			
60255800	MANHOLES TO BE ADJUSTED WITH TYPE I FRAME, CLOSED LID	EACH	1	1			

• NON-PARTICIPATING

• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 DATE: _____

DRAWN BY _____
 CHECKED BY _____

PLOT DATE = Thu Sep 28 14:50:18 2007
 FILE NAME = c:\pwork\proj\20070928\20070928.dgn
 USER = c:\pwork\proj\20070928\20070928.dgn
 USER NAME = c:\pwork\proj\20070928\20070928.dgn