

SCHEDULE OF QUANTITIES

CONTRACT NO. 64931

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCK ISLAND	139	13
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

*(IL 5)

ITEM NO.	DESCRIPTION	CU YD	LOCATION	OFFSET	REMARKS
20200100	EARTH EXCAVATION				
	CU YD LOCATION				
	IL 5/IL 92				
	325 620+50.0 TO 628+50.0				
	325 SUBTOTAL				
	IL 84				
	2530 135+00.0 TO 141+50.0				
	2530 SUBTOTAL				
	2855 TOTAL				
20400800	FURNISHED EXCAVATION				
	CU YD LOCATION				
	Ramp CA				
	385 10+50.0 TO 12+75.0				TEMPORARY PAVEMENT STAGE 1
	385 TOTAL				
28000400	PERIMETER EROSION BARRIER				
	FOOT LOCATION				
	1000 TO BE USED AS NEEDED				
	1000 TOTAL				
28000500	INLET AND PIPE PROTECTION				
	EACH LOCATION				
	IL 5/IL 92				
	1 604+09.9 CL				
	1 608+09.0 CL				
	1 611+09.0 CL				
	1 614+09.6 CL				
	1 617+10.6 CL				
	5 TOTAL				
28100107	STONE RIPRAP CLASS A4				
	SQ YD LOCATION				
	IL 5/IL 92				
	7 611+09.0 RT				5' x 12'
	10 614+09.0 RT				UNDER END SECTION 5' x 18'
	10 617+10.0 RT				UNDER END SECTION 5' x 18'
	27 SUBTOTAL				
	RAMP BD				
	190 3+21.5 TO 7+48.3 RT				4" WIDE
	190 SUBTOTAL				
	IL 84				
	2 134+14.0 LT				4' X 4' AT ENDS OF CONCRETE HEADWALL FOR PIPE DRAINS
	2 139+75.0 RT				4' X 4' AT ENDS OF CONCRETE HEADWALL FOR PIPE DRAINS
	2 141+05.9 LT				4' X 4' AT ENDS OF CONCRETE HEADWALL FOR PIPE DRAINS
	6 SUBTOTAL				
	223 TOTAL				
28100208	STONE RIPRAP CLASS A4 (SPECIAL)				
	TON LOCATION				
	RAMP BD				
	2792 7+48.3 TO 16+07.5 RT				BREAK-UP PAVED DITCH TO BE USED AS RIPRAP
	2792 TOTAL				
28200200	FILTER FABRIC				
	SQ YD LOCATION				
	IL 5/IL 92				
	7 611+09.0				
	10 614+09.0				
	10 617+10.0				
	27 SUBTOTAL				
	RAMP BD				
	190 3+21.5 TO 7+48.3				4" WIDE
	190 SUBTOTAL				
	IL 84				
	2 134+14.0 LT				4' X 4' AT ENDS OF CONCRETE HEADWALL FOR PIPE DRAINS
	2 139+75.0 RT				4' X 4' AT ENDS OF CONCRETE HEADWALL FOR PIPE DRAINS
	2 141+05.9 LT				4' X 4' AT ENDS OF CONCRETE HEADWALL FOR PIPE DRAINS
	6 SUBTOTAL				
	223 TOTAL				
31100910	SUB BASE GRANULAR MATERIAL TYPE A 12"				
	SQ YD LOCATION				
	IL 5/IL 92				
	2143 606+84.9 TO 618+32.6				MEDIAN
	367 618+00.0 TO 622+34.4				SHOULDER
	356 621+00.0 TO 622+45.0				RAMP
	404 621+00.0 TO 622+58.0				MAINLINE
	71 621+00.0 TO 622+60.2				UNDER BARRIER WALL
	445 621+00.0 TO 622+73.3				MAINLINE
	93 621+00.0 TO 622+75.0				GORE
	282 621+00.0 TO 622+82.5				RAMP
	169 621+00.0 TO 622+87.4				SHOULDER
	517 624+34.8 TO 628+06.4				SHOULDER
	71 624+39.8 TO 625+58.2				RAMP
	286 624+44.5 TO 625+58.2				MAINLINE
	44 624+57.6 TO 625+58.2				UNDER BARRIER WALL
	245 624+59.8 TO 625+58.2				MAINLINE
	108 624+72.8 TO 625+58.2				RAMP
	50 624+79.7 TO 625+58.2				SHOULDER
	5651 SUBTOTAL				
	IL 84				
	644 135+38.6 TO 139+89.8				SHOULDER
	670 136+42.5 TO 140+05.9				SHOULDER
	1480 136+42.5 TO 139+89.8				MAINLINE & RAMPS
	926 136+42.5 TO 139+89.8				MAINLINE & RAMPS
	3719 SUBTOTAL				
	9370 TOTAL				
31200100	STABILIZED SUB-BASE 4"				
	SQ YD LOCATION				
	IL 84				
	1596 136+42.5 TO 139+89.8				MAINLINE & RAMP
	1042 136+42.5 TO 139+89.8				MAINLINE
	2638 TOTAL				
40600635	LEVELING BINDER (MACHINE METHOD) N 70				
	TON LOCATION				
	IL 5/IL 92				
	51 625+58.2 TO 626+50.0				LT
	9 625+58.2 TO 626+50.0				CL
	51 625+58.2 TO 626+50.0				RT
	22 625+58.2 TO 626+50.0				RT
	105 625+58.2 TO 626+50.0				RT
	238 TOTAL				

PLOT DATE = Thu Aug 23 17:46:59 2007
 FILE NAME = c:\pwork\64931\28100208\28100208.dgn
 USER NAME = c:\pwork\64931\64931

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE:	VERT. DATE	HORIZ. DATE
DRAWN BY		CHECKED BY