CONTRACT NO. 64931

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCKISLAND	139	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(IL 5)

SCHEDULE OF QUANTITIES

40600990 TEMPORARY RAMP

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
20	632+08.2			LT	
20	632+08.2			RT	
40	**TOTAL**				

40603310 HOT MIX ASPHALT SURFACE COURSE, MIX "C" N50

TON	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
56	624+34.8	TO	628+06.4	LT	SHOULDER
68	624+79.7	TO	632+33.8	RT	SHOULDER
124	SUBTOTAL				
	IL 84				
69	135+38.6	TO	139+89.8	RT	SHOULDER
73	136+42.5	TO	140+05.9	LT	SHOULDER
142	SUBTOTAL				
266	**TOTAL**				

40603335 HOT MIX ASPHALT SURFACE COURSE, MIX "D" N50

TON	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
38	618+00.0	TO	622+34.4	LT	SHOULDER
18	621+00.0	TO	622+87.4	RT	SHOULDER
56	**TOTAL**				

40603340 HOT MIX ASPHALT SURFACE COURSE, MIX "D", N 70

TON	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
27	625+58.2	TO	626+50.0	LT	MAINLINE
5	625+58.2	TO	626+50.0	CL	MEDIAN
27	625+58.2	TO	626+50.0	RT	MAINLINE
12	625+58.2	TO	626+50.0	RT	RAMP
169	626+50.0	TO	632+10.4	LT	MAINLINE
28	626+50.0	TO	632+17.2	CL	MEDIAN
171	626+50.0	TO	632+24.0	RT	MAINLINE
27	626+50.0	TO	630+46.3	RT	RAMP
466	**TOTAL**				

42000301 PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
2143	606+84.9	TO	618+32.6	CL	MEDIAN

42001165 BRIDGE APPROACH PAVEMENT

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
364	622+59.0	TO	622+90.2		
320	624+26.2	TO	624+59.1		
684	**TOTAL**				

42001200 PAVEMENT FABRIC

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
2143	606+84.9	TO	618+32.6	CL	MEDIAN
356	621+00.0	TO	622+45.0	LT	RAMP
404	621+00.0	TO	622+58.0	LT	MAINLINE
71	621+00.0	TO	622+60.2	CL	MEDIAN
445	621+00.0	TO	622+73.3	RT	MAINLINE
93	621+00.0	TO	622+75.0	RT	GORE
282	621+00.0	TO	622+82.5	RT	RAMP
71	624+39.8	TO	625+58.2	LT	RAMP
286	624+44.5	TO	625+58.2	LT	MAINLINE
44	624+57.6	TO	625+58.2	CL	MEDIAN
245	624+59.8	TO	625+58.2	RT	MAINLINE
108	624+72.8	TO	625+58.2	RT	RAMP
4547	**TOTAL**				

42001300 PROTECTIVE COAT

SQ YD	LOCATION			OFFSET	REMARKS
	IL5/IL92				
890	621+00.0	TO	622+82.5	RT	MAINLINE, MEDIAN, AND RAMP
397	624+39.8	TO	625+58.2	RT	MAINLINE, MEDIAN, AND RAMP
1287	SUBTOTAL				
	IL 84				
2406	136+42.5	TO	139+89.8		MAINLINE AND RAMPS
2406	SUBTOTAL				
3693	**TOTAL**				

42001420 BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
356	621+00.0	TO	622+45.0	LT	RAMP
404	621+00.0	TO	622+58.0	LT	MAINLINE
71	621+00.0	TO	622+60.2	CL	MEDIAN
445	621+00.0	TO	622+73.3	RT	MAINLINE
93	621+00.0	TO	622+75.0	RT	GORE
282	621+00.0	TO	622+82.5	RT	RAMP
71	624+39.8	TO	625+58.2	LT	RAMP
286	624+44.5	TO	625+58.2	LT	MAINLINE
44	624+57.6	TO	625+58.2	CL	MEDIAN
245	624+59.8	TO	625+58.2	RT	MAINLINE
108	624+72.8	TO	625+58.2	RT	RAMP
2404	**TOTAL**				

42100100 CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 8"

SQ YD	LOCATION			OFFSET	REMARKS
	IL 84				
1480	136+42.5	TO	139+89.8	LT	MAINLINE & RAMP
926	136+42.5	TO	139+89.8	RT	MAINLINE
2406	**TOTAL**				

42100700 PAVEMENT REINFORCEMENT 8"

SQ YD	LOCATION			OFFSET	REMARKS
	IL 84				
1480	136+42.5	TO	139+89.8	LT	MAINLINE & RAMP
926	136+42.5	TO	139+89.8	RT	MAINLINE
2406	**TOTAL**				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Thu Aug 23 17:05:18 2007
FILE NAME = c:\projects\2262203\d262203sp1.dgn
PLOT SCALE = 50.0000 ' / in.
USER NAME = ocerwil1cpg