

# SCHEDULE OF QUANTITIES

CONTRACT NO. 64931				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCKISLAND	139	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*CIL 51				

44000100	PAVEMENT REMOVAL		OFFSET	REMARKS
SQ YD	LOCATION			
	IL 5/IL 92			
201	621+00.0	TO	622+17.1	LT RAMP
99	621+00.0	TO	622+19.4	LT GORE
322	621+00.0	TO	622+31.7	LT MAINLINE
82	621+00.0	TO	622+35.0	CL MEDIAN
370	621+00.0	TO	622+47.6	RT MAINLINE
83	621+00.0	TO	622+49.9	RT GORE
243	621+00.0	TO	622+56.8	RT RAMP
65	624+40.7	TO	625+58.2	LT RAMP
279	624+45.3	TO	625+58.2	LT MAINLINE
56	624+58.2	TO	625+58.2	CL MEDIAN
236	624+61.2	TO	625+58.2	RT MAINLINE
109	624+73.6	TO	625+58.2	RT RAMP
2145	SUBTOTAL			
	IL 84			
933	136+42.5	TO	139+89.8	RT MAINLINE
930	136+42.5	TO	139+89.8	LT MAINLINE
516	136+42.5	TO	139+89.8	LT GORE & RAMP
2378	SUBTOTAL			
4523	TOTAL			

44002020	CONCRETE MEDIAN SURFACE REMOVAL		OFFSET	REMARKS
SQ FT	LOCATION			
	IL 5/IL 92			
13880	606+84.9	TO	617+81.2	
13880	SUBTOTAL			
	IL 84			
4995	136+42.5	TO	139+89.8	
4995	SUBTOTAL			
18875	TOTAL			

44004250	PAVED SHOULDER REMOVAL		OFFSET	REMARKS
SQ YD	LOCATION			
	IL 5/IL 92			
202	618+00.0	TO	621+00.0	LT
286	625+58.2	TO	628+06.4	LT
488	SUBTOTAL			
	IL 84			
458	135+38.6	TO	139+89.8	RT
472	136+42.5	TO	141+05.9	LT
930	SUBTOTAL			
1418	TOTAL			

44000157	HOT MIX ASPHALT SURFACE REMOVAL, 2"		OFFSET	REMARKS
SQ YD	LOCATION			
	IL 5/IL 92			
1752	625+58.2	TO	632+10.4	LT MAINLINE
1768	625+58.2	TO	632+24.5	RT MAINLINE
343	625+58.2	TO	630+46.3	RT TAPER
563	625+58.2	TO	632+33.8	RT SHOULDER
4426	TOTAL			

48203021	HOT-MIX ASPHALT SHOULDERS, 6"		OFFSET	REMARKS
SQ YD	LOCATION			
	IL 5/IL 92			
343	618+00.0	TO	622+34.4	LT
159	621+00.0	TO	622+87.4	RT
497	624+34.8	TO	628+06.4	LT
46	624+79.7	TO	625+58.2	RT
1044	SUBTOTAL			
	IL 84			
549	135+38.6	TO	139+89.8	RT
594	136+42.6	TO	141+05.9	LT
1142	SUBTOTAL			
2186	TOTAL			

44000300	CURB REMOVAL		OFFSET	REMARKS
FOOT	LOCATION			
	IL 5/IL 92			
80	621+25.0	TO	622+05.0	LT
80	621+79.0	TO	622+59.0	RT
160	TOTAL			

50157300	PROTECTIVE SHIELD		OFFSET	REMARKS
SQ YD	LOCATION			
	IL 5/IL 92			
2243	622+35.0	TO	624+58.2	
2243	TOTAL			

44000500	COMBINATION CURB AND GUTTER REMOVAL		OFFSET	REMARKS
FOOT	LOCATION			
	IL 5/IL 92			
1104	606 + 84.94	TO	617 + 81.2	MEDIAN
1104	SUBTOTAL			
	IL 84			
695	136+42.5	TO	139+89.8	
695	SUBTOTAL			
1799	TOTAL			

5421A018	PIPE CULVERTS, CLASS A, TYPE I, 18" (TEMPORARY)		OFFSET	REMARKS
FOOT	LOCATION			
	RAMP CA			
49	11+95.0			34 Deg Skew
49	TOTAL			

44001980	CONCRETE BARRIER REMOVAL		OFFSET	REMARKS
FOOT	LOCATION			
	IL 5/IL 92			
81	621+34.4	TO	622+15.3	SLIP FORM 0.8' WIDE
19	622+15.3	TO	622+33.8	SLIP FORM TRANSITION 0.8' - 1.66'
17	624+60.5	TO	624+77.7	SLIP FORM TRANSITION 0.8' - 1.66'
85	624+77.7	TO	625+62.2	SLIP FORM 0.8' WIDE
201	TOTAL			

542D0217	PIPE CULVERTS, CLASS D, TYPE I, 12"		OFFSET	REMARKS
FOOT	LOCATION			
	IL 5			
15	622+34.6			LT
18	622+82.4			RT
33	TOTAL			

PLOT DATE = Thu Aug 23 17:05:12 2007  
 PLOT SCALE = 8X8  
 USER NAME = cccvcl09g

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY