

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#595	5HBR	ROCKISLAND	139	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\*(IL 5)

54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"				
EACH	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
1	617+10.0	62.5' RT			
<b>1</b>	<b>TOTAL</b>				

54215547	METAL END SECTIONS 12"				
EACH	LOCATION	OFFSET		REMARKS	
	IL 5				
1	622+34.6	60' LT			
1	622+82.4	60' RT			
<b>2</b>	<b>TOTAL</b>				

55037800	STORM SEWERS TO BE CLEANED 12"				
FOOT	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
71	605+09.9	RT			
93	608+09.0	RT			
<b>164</b>	<b>TOTAL</b>				

55100500	STORM SEWER REMOVAL 12"				
FOOT	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
12	605+09.9	CL			
16	608+09.0	CL			
12	611+09.0	CL			
14	614+09.6	CL			
9	617+10.6	CL			
<b>63</b>	<b>TOTAL</b>				

60100060	CONCRETE HEADWALL FOR PIPE DRAINS				
EACH	LOCATION	OFFSET		REMARKS	
1	137+14.0	LT		72.5'	
1	139+75.0	RT		51.7'	
1	141+05.9	LT		78'	
<b>3</b>	<b>TOTAL</b>				

60107600	PIPE UNDERDRAINS 4"				
FOOT	LOCATION	OFFSET		REMARKS	
	IL 84				
451	135+38.6 TO 139+89.9	RT			
463	136+42.5 TO 141+05.9	LT			
84	136+50.0	AR			
28	137+14.0	LT			
80	138+00.0	AR			
103	139+75.0	AR			
25	141+05.9	LT			
<b>1234</b>	<b>TOTAL</b>				

60238630	INLETS, TYPE A, WITH SPECIAL FRAME, OPEN LID				
EACH	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
1	622+34.6	LT			
1	622+82.4	RT			
<b>2</b>	<b>TOTAL</b>				

60247160	DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATE				
EACH	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
1	605+09.9	CL		STAGE 2	
1	608+09.0	CL		STAGE 2	
1	611+09.5	CL		STAGE 2	
1	614+09.6	CL		STAGE 2	
1	617+10.0	CL		STAGE 2	
<b>5</b>	<b>TOTAL</b>				

60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID				
EACH	LOCATION	OFFSET		REMARKS	
	RAMP AD				
1	15+80.7	RT		PAVED DITCH	
<b>1</b>	<b>TOTAL</b>				

60260100	INLETS TO BE ADJUSTED				
EACH	LOCATION	OFFSET		REMARKS	
	IL 84				
1	137+16.5			MEDIAN	
<b>1</b>	<b>TOTAL</b>				

60265108	INLETS TO BE RECONSTRUCTED WITH NEW FRAME AND GRATE, SPECIAL				
EACH	LOCATION	OFFSET		REMARKS	
	RAMP AD				
1	15+89.7	RT		PAVED DITCH	
<b>1</b>	<b>TOTAL</b>				

60500070	REMOVING MANHOLES TO MAINTAIN FLOW				
EACH	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
1	605+09.9	CL		STAGE 2	
1	611+09.5	CL		STAGE 2	
1	617+10.0	CL		STAGE 2	
<b>3</b>	<b>TOTAL</b>				

60500090	REMOVING INLETS TO MAINTAIN FLOW				
EACH	LOCATION	OFFSET		REMARKS	
	IL 5/IL 92				
1	605+09.9	8' LT		STAGE 2	
1	608+09.0	8' LT		STAGE 2	
1	611+09.5	8' LT		STAGE 2	
1	614+09.6	8' LT		STAGE 2	
1	617+10.0	8' LT		STAGE 2	
<b>5</b>	<b>TOTAL</b>				

60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24				
FOOT	LOCATION	OFFSET		REMARKS	
	IL 84				
181	137+71.1 TO 138+61.3			MEDIAN	
<b>181</b>	<b>TOTAL</b>				

60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24				
FOOT	LOCATION	OFFSET		REMARKS	
	IL 84				
117	136+90.6 TO 137+49.2			MEDIAN	
117	138+83.2 TO 139+41.8			MEDIAN	
<b>234</b>	<b>TOTAL</b>				

60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)				
FOOT	LOCATION	OFFSET		REMARKS	
	IL 84				
96	136+42.5 TO 136+90.6			TAPER 9" TO 2" CURB	
44	137+49.2 TO 137+71.1			TAPER 2" TO 6" CURB	
44	138+61.3 TO 138+83.2			TAPER 6" TO 2" CURB	
96	139+41.8 TO 139+89.8			TAPER 2" TO 9" CURB	
<b>280</b>	<b>TOTAL</b>				

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. DATE      HORIZ. DATE      DRAWN BY      CHECKED BY

PLOT DATE = Thu Aug 23 17:05:13 2007  
 PLOT SCALE = 8X11  
 USER NAME = ccsallong