CONTRACT NO. 64931

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCKISLAND	139	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(IL 5)

SCHEDULE OF QUANTITIES

60618300 CONCRETE MEDIAN SURFACE 4"

SQ FT	LOCATION			OFFSET	REMARKS
	IL 84				
4509	136+42.5	TO	139+89.8		
4509	**TOTAL**				

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

FOOT	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
25	621+60.4	TO	621+85.4	LT	
25	SUBTOTAL				
	IL 84				
200	136+22.6	TO	138+22.6	RT	
200	138+21.7	TO	140+21.7	LT	
400	SUBTOTAL				
425	**TOTAL**				

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2

EACH	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
1	621+47.5	TO	621+60.4	LT	
1	SUBTOTAL				
	IL 84				
1	138+09.2	TO	138+21.7	LT	
1	138+22.6	TO	138+35.1	RT	
2	SUBTOTAL				
3	**TOTAL**				

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
1	621+85.4	TO	622+29.1	LT	
1	622+42.9	TO	622+86.6	RT	
1	624+35.6	TO	624+79.3	LT	
3	**TOTAL**				

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
1	621+92.9	TO	622+42.9	RT	
1	**TOTAL**				

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

EACH	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
1	624+76.7	TO	625+29.3	LT	
1	SUBTOTAL				
	IL 84				
1	135+72.6	TO	136+22.6	RT	
1	140+21.7	TO	140+71.7	LT	
2	SUBTOTAL				
3	**TOTAL**				

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
120	621+88.7	TO	623+08.7	LT	
150	622+11.4	TO	623+61.4	RT	
80	624+36.8	TO	625+16.8	LT	
20	624+81.9	TO	625+01.9	RT	
370	SUBTOTAL				
	IL 84				
178	137+74.0	TO	139+52.0	LT	
165	136+96.9	TO	138+61.9	RT	
343	SUBTOTAL				
713	**TOTAL**				

63500105 DELINEATORS

EACH	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
1	605+09.9			RT	STORM SEWER OUTLET
1	608+09.0			RT	STORM SEWER OUTLET
1	611+09.5			RT	STORM SEWER OUTLET
1	614+09.6			RT	STORM SEWER OUTLET
1	617+10.0			RT	STORM SEWER OUTLET
1	621+92.9			RT	GUARDRAIL
1	625+29.3			LT	GUARDRAIL
7	SUBTOTAL				
	IL 84				
1	135+72.6			RT	GUARDRAIL
1	140+71.7			LT	GUARDRAIL
2	SUBTOTAL				
9	**TOTAL**				

63700115 CONCRETE DOUBLE BARRIER, DOUBLE FACE

FOOT	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
525	604+91.1	TO	610+16.1		STAGE 2
1263	610+16.1	TO	622+91.1		
588	625+49.7	TO	630+37.2		
2375	**TOTAL**				

63700805 CONCRETE BARRIER TRANSITION

FOOT	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
21	604+70.4	TO	604+91.1		
13	622+78.6	TO	622+91.1		
23	624+26.8	TO	624+49.7		
56	**TOTAL**				

70300100 SHORT TERM PAVEMENT MARKING

FOOT	LOCATION			OFFSET	REMARKS
530.0	625+58.2	TO	632+10.4		WHITE LANE LINES
530.0	625+58.2	TO	632+10.4		YELLOW EDGE OF PAVEMENT
530.0	625+58.2	TO	632+10.4		WHITE EDGELINES
1590.0	**TOTAL**				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Thu Sep 20 14:20:14 2007
FILE NAME = d:\projects\2283283\u8283sp1.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = costellopg