CONTRACT NO. 64931

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCKISLAND	139	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(IL 5)

SCHEDULE OF QUANTITIES

70300200 TEMPORARY PAVEMENT MARKING

FOOT	LOCATION			OFFSET	REMARKS
	IL 5/IL92				
5476	604+70.0	TO	632+08.2	LT & RT	YELLOW CENTERLINE
5476	604+70.4	TO	632+08.2	LT & RT	WHITE EDGELINES
1369	604+70.4	TO	632+08.2	LT & RT	WHITE SKIPDASH
12320	SUBTOTAL				
	RAMP CA				
157	60+42.7	TO	66+69.6	RT	WHITE SKIPDASH
250	52+50.0	TO	55+00.0	LT	YELLOW EDGELINE
1585	52+50.0	TO	60+42.7	RT	8" WHITE EDGELINE
543	55+00.0	TO	60+42.7	LT	WHITE EDGELINES
	RAMP AD				
1002	9+92.6	TO	19+94.2	RT	WHITE EDGELINES
134	9+92.6	TO	15+29.8	LT	WHITE SKIPDASH
595	15+29.8	TO	18+27.5	LT	8" WHITE EDGELINE
167	18+27.5	TO	19+94.2	LT	YELLOW EDGELINE
	RAMP AD TO CA				
264	138+57.7	TO	139+89.8	LT	8" WHITE EDGELINES
4697	SUBTOTAL				
	IL 84				
451	135+38.6	TO	139+89.9	RT	WHITE EDGELINES
54	136+42.5	TO	138+57.5	LT	WHITE SKIPDASH
174	136+42.5	TO	139+89.9	LT & RT	WHITE SKIPDASH
363	136+42.5	TO	140+05.9	RT	WHITE EDGELINES
695	136+42.5	TO	139+89.9	LT & RT	YELLOW EDGELINE
1737	SUBTOTAL				
18754	**TOTAL**				

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION			OFFSET	REMARKS
	STAGE 1				
	RAMP CA				
272	52+50.0	TO	MAINLINE	LT	YELLOW
150	53+50.0	TO	MAINLINE	RT	WHITE
	STAGE 2				
	IL5 / IL 92				
1000	586+71.5	TO	596+71.5	RT	YELLOW IF 701401 IS USED FOR GREATER THAN 14 DAYS
	STAGE 3				
2958	600+79.6	TO	630+37.2	RT	YELLOW
1737	613+00.0	TO	630+37.2	LT	YELLOW
500	615+80.0	TO	620+80.0	RT	WHITE
178	616+06.0	TO	617+84.2	LT	WHITE
209	19+94.2	TO	617+84.2	RT	YELLOW - RAMP TO MAINLINE
1776	19+94.2	TO	633+50.0	LT	WHITE RAMP TO MAINLINE
354	623+80.0	TO	627+34.0	RT	WHITE
618	627+29.0	TO	633+47.0	LT	WHITE - RAMP TO MAINLINE
	STAGE 4				
1000	587+68.0	TO	597+68.0	RT	WHITE
118	602+67.0	TO	604+50.0	RT	WHITE - MAINLINE TO RAMP
241	605+67.0	TO	608+10.0	RT	WHITE - MAINLINE TO RAMP
1978	610+68.0	TO	630+46.0	RT	WHITE
1970	610+68.0	TO	630+46.0	RT	YELLOW
1675	613+63.0	TO	630+38.0	LT	YELLOW
1321	616+62.0	TO	629+83.0	LT	WHITE
	STAGE 4				
247	631+00.0	TO	633+47.0	LT	WHITE RAMP TO MAINLINE
1000	641+00.0	TO	651+00.0	LT	WHITE
315	TEMP RAMP				YELLOW
436	TEMP RAMP				WHITE
100	TEMP RAMP				STOP BAR 2-4" LINES 50'
20152	SUBTOTAL				
	IL 84				
391	RAMP AC				WHITE
748	RAMP AD				WHITE
200	STOP BAR				2-4" LINES 50'
1083	RAMP AC				WHITE
2421	SUBTOTAL				
22573	**TOTAL**				

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
530.0	625+58.2	TO	632+10.4		SHORT TERM REMOVAL
4103.0	604+70.0	TO	632+08.2		TEMPORARY REMOVAL
	STAGE 1				
	RAMP CA				
91	52+50.0	TO	MAINLINE	LT	
50	53+50.0	TO	MAINLINE	RT	
	STAGE 2				
	IL5 / IL 92				
333	586+71.5	TO	596+71.5	RT	
	STAGE 3				
986	600+79.6	TO	630+37.2	RT	
579	613+00.0	TO	630+37.2	LT	
167	615+80.0	TO	620+80.0	RT	
59	616+06.0	TO	617+84.2	LT	
70	19+94.2	TO	617+84.2	RT	
592	19+94.2	TO	633+50.0	LT	
118	623+80.0	TO	627+34.0	RT	
206	627+29.0	TO	633+47.0	LT	
	STAGE 4				
333	587+68.0	TO	597+68.0	RT	
39	602+67.0	TO	604+50.0	RT	
80	605+67.0	TO	608+10.0	RT	
659	610+68.0	TO	630+46.0	RT	
657	610+68.0	TO	630+46.0	RT	
558	613+63.0	TO	630+38.0	LT	
440	616+62.0	TO	629+83.0	LT	
	STAGE 4				
82	631+00.0	TO	633+47.0	LT	
333	641+00.0	TO	651+00.0	LT	
105	TEMP RAMP				
145	TEMP RAMP				
33	TEMP RAMP				
11350	SUBTOTAL				
844	RAMP CA				TEMPORARY REMOVAL
632	RAMP AD				TEMPORARY REMOVAL
88	RAMP AD TO CA				TEMPORARY REMOVAL
1564	SUBTOTAL				
	IL 84				
578	135+38.6	TO	140+05.9		TEMPORARY REMOVAL
130	RAMP AC				
249	RAMP AD				
67	STOP BAR				
361	RAMP AC				
1385	SUBTOTAL				
14299	**TOTAL**				

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION			OFFSET	REMARKS
	IL5/IL92				
850	610+16.1	TO	618+59.0		STAGE 3
750	619+78.9	TO	627+29.0		STAGE 3
500	621+09.0	TO	625+87.2		STAGE 3
100	626+79.0	TO	627+55.7		STAGE 4
2200					
	IL 84				
350	135+92.8	TO	139+42.9		STAGE 3A
300	137+28.2	TO	140+28.2		STAGE 3A
50	140+05.3	TO	140+55.3		STAGE 4B
700	SUBTOTAL				
2900	**TOTAL**				

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Thu Sep 28 14:28:15 2007
FILE NAME = c:\pw_pw1\projects\p285283\d285283sp1.dgn
PLOT SCALE = 50.0000 ' / in.
USER NAME = scottd1