

# PATCHING SCHEDULE

CONTRACT NO. 64931				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCKISLAND	139	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*(IL 5)				

## CLASS B PATCHING

12 FEET LANE WIDTH

STATION	REMARKS	LENGTH OF PATCH		AREA OF PATCHES								SAW CUTS (3W+?L) (foot)	DOWEL BARS (each)	TIE BARS (each)	PAVEMENT FABRIC (yd <sup>2</sup> )	GEOTECHNICAL REINFORCEMENT		GRAN SUB-GRADE REPLACEMENT	
		LT LANE (foot)	RT LANE (foot)	TYPE 1		TYPE 2		TYPE 3		TYPE 4						LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )	LT LANE (yd <sup>3</sup> )	RT LANE (yd <sup>3</sup> )
				LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )	LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )	LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )	LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )								
+ 00																			
605 + 29	WB	25								33.3		61	20	12	33.3	33.3		5.6	
605 + 68	WB		40								53.3	76	20	19	53.3		53.3	8.9	
607 + 12	WB		6				8.0					42	20				8.0	1.3	
607 + 65	WB		6				8.0					42	20				8.0	1.3	
607 + 93	WB		6				8.0					42	20				8.0	1.3	
608 + 45	WB		6				8.0					42	20				8.0	1.3	
608 + 51	WB	6			8.0							42	20			8.0		1.3	
608 + 69	WB		6				8.0					42	20				8.0	1.3	
608 + 79	WB	6			8.0							42	20			8.0		1.3	
608 + 97	WB		6				8.0					42	20				8.0	1.3	
611 + 96	WB		6				8.0					42	20				8.0	1.3	
612 + 55	WB		18						24.0			54	20		24.0		24.0	4.0	
614 + 29	EB		6				8.0					42	20				8.0	1.3	
614 + 32	WB		22								29.3	58	20	10	29.3		29.3	4.9	
614 + 64	WB	6	6		8.0	8.0						78	40			8.0	8.0	1.3	
614 + 70	EB	6	6		8.0	8.0						78	40			8.0	8.0	1.3	
615 + 66	WB		6				8.0					42	20				8.0	1.3	
615 + 93	EB	55								73.3		91	20	27	73.3	73.3		12.2	
616 + 7	WB	15						20.0				51	20		20.0	20.0		3.3	
616 + 85	EB	6			8.0							42	20			8.0		1.3	
617 + 42	EB	8			10.7							44	20			10.7		1.8	
618 + 26	WB		6				8.0					42	20				8.0	1.3	
618 + 36	EB	6			8.0							42	20			8.0		1.3	
629 + 24	EB	6	6		8.0							78	40			8.0		1.3	
629 + 24	WB	6	6		8.0							78	40			8.0		1.3	
<b>SUB-TOTALS</b>					<b>75</b>	<b>96</b>	<b>20</b>	<b>24</b>	<b>107</b>	<b>83</b>					<b>201</b>	<b>203</b>	<b>34</b>	<b>36</b>	
<b>TOTALS</b>					<b>171</b>		<b>44</b>		<b>190</b>		<b>1335</b>	<b>540</b>	<b>68</b>		<b>233</b>	<b>404</b>		<b>70</b>	

PLOT DATE = Thu Sep 28 14:56:07 2007  
 FILE NAME = c:\p020203\080203pl.dgn  
 PLOT SCALE = 60,0000 / IN.  
 USER NAME = costellojg

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

## PATCHING SCHEDULE