

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120T-2	OGLE	59	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION
	IL 72
1	Sta 2108+00 40' LT
1	Sta 2109+00 55' LT
1	Sta 2109+50 90' LT
1	Sta 2110+50 90' LT
1	Sta 2111+00 50' LT
1	Sta 2112+00 40' LT
1	Sta 2107+50 40' RT
1	Sta 2108+00 55' RT
1	Sta 2109+00 70' RT
1	Sta 2110+00 70' RT
1	Sta 2111+00 50' RT
1	Sta 2112+00 40' RT
1	Sta 2130+00 40' LT
1	Sta 2131+00 50' LT
1	Sta 2132+00 85' LT
1	Sta 2132+75 85' LT
1	Sta 2133+00 45' LT
1	Sta 2133+390940' LT
1	Sta 2130+00 40' RT
1	Sta 2130+75 65' RT
1	Sta 2132+00 65' RT
1	Sta 2133+00 40' LT
22	TOTAL

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION
	IL 72
670	Sta 2106+35 - 2112+95 Stage 1 - White EOP
340	Sta 2108+00 - 2111+35 Stage 1 - White EOP
670	Sta 2106+35 - 2112+95 Stage 2 - White EOP
310	Sta 2108+15 - 2111+20 Stage 2 - White EOP
735	Sta 2128+25 - 2135+20 Stage 3 - White EOP
430	Sta 2129+50 - 2133+75 Stage 3 - White EOP
710	Sta 2128+25 - 2135+20 Stage 4 - White EOP
365	Sta 2129+85 - 2133+45 Stage 4 - White EOP
4230	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	IL 72
310	Sta 2108+10 - 2111+20 Stage 1
350	Sta 2129+65 - 2133+15 Stage 3
660	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	IL 72
310	Sta 2108+10 - 2111+20 Stage 2
350	Sta 2129+85 - 2133+35 Stage 4
660	TOTAL

70300570 PAVEMENT MARKING TAPE, TYPE III 24"

FOOT	LOCATION
	IL 72
13	Sta 2106+35 Stop Bar
13	Sta 2112+95 Stop Bar
13	Sta 2128+25 Stop Bar
13	Sta 2135+20 Stop Bar
10	Crill Rd Stop Bar
62	TOTAL

66700305 PERMANENT SURVEY MARKER, TYPE II

EACH	LOCATION
	IL 72
1	As Directed by the Resident (Located at 1st culvert)
1	As Directed by the Resident (Located on hill between culverts)
1	As Directed by the Resident (Located at 2nd culvert)
3	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SO FT	LOCATION
	IL 72
223.3	Sta 2106+35 - 2112+95 EOP Tape, Line 4"
113.3	Sta 2108+00 - 2111+35 EOP Tape, Line 4"
223.3	Sta 2106+35 - 2112+95 EOP Tape, Line 4"
103.3	Sta 2108+15 - 2111+20 EOP Tape, Line 4"
245.0	Sta 2128+25 - 2135+20 EOP Tape, Line 4"
143.3	Sta 2129+50 - 2133+75 EOP Tape, Line 4"
236.7	Sta 2128+25 - 2135+20 EOP Tape, Line 4"
121.7	Sta 2129+85 - 2133+45 EOP Tape, Line 4"
26.0	Sta 2106+35 Stop Bar Tape, Line 24"
26.0	Sta 2112+95 Stop Bar Tape, Line 24"
26.0	Sta 2128+25 Stop Bar Tape, Line 24"
26.0	Sta 2135+20 Stop Bar Tape, Line 24"
20.0	Crill Rd Stop Bar Tape, Line 24"
1533.9	TOTAL

70106700 TEMPORARY RUMBLE STRIPS

EACH	LOCATION
	IL 72
6	As Directed by the Resident (Located at 1st culvert)
6	As Directed by the Resident (Located at 2nd culvert)
12	TOTAL

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. _____
 DATE _____ HORIZ. _____

DRAWN BY _____
 CHECKED BY _____