

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	5 BR-1	La SALLE	32	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED 20% STATE

ROADWAY EX SN 050-0067
PR SN 050-2043

CONSTRUCTION TYPE CODE
1000 X080-2A

- △
- △
- △
- △
- △
- △

CODE NO	ITEM	UNIT	TOTAL QNTY	1000	X080-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	884	884	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	80	80	
20101100	TREE TRUNK PROTECTION	EACH	6	6	
20200100	EARTH EXCAVATION	CU YD	1797	1797	
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	95	95	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	3570	3570	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4590	4590	
25000200	SEEDING, CLASS 2	ACRE	1	1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	85.3	85.3	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	85.3	85.3	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	85.3	85.3	
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
25100630	EROSION CONTROL BLANKET	SQ YD	2141	2141	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	95	95	
28000300	TEMPORARY DITCH CHECKS	EACH	8	8	
28000400	PERIMETER EROSION BARRIER	FOOT	2077	2077	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	842	842	
28200200	FILTER FABRIC	SQ YD	821	821	
35501331	HOT-MIX ASPHALT BASE COURSE, 11 3/4"	SQ YD	346	346	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	211.6	211.6	
40600300	AGGREGATE (PRIME COAT)	TON	5.3	5.3	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	86	86	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	463	463	
40600990	TEMPORARY RAMP	SQ YD	48	48	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	230	230	
44000100	PAVEMENT REMOVAL	SQ YD	205	205	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	2094	2094	
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	471	471	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	53	53	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	16	16	
48203029	HOT-MIX ASPHALT SHOULDERS 8"	SQ YD	1692	1692	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	17	17	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	61	61	
50800105	REINFORCEMENT BARS	POUND	3580		3580
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1360		1360

△ SPECIALTY ITEM

PLOT DATE = 7/26/2007
 FILE NAME = c:\projects\66449\roadway\summary of quantities.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = duncanb3

COOMBE-BLOXDORF P.C.
 Engineers/Land Surveyors
 Springfield, Illinois
 Design Firm License No. 184-002703

REVISIONS	
NAME	DATE
BDD	4/11/07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL ROUTE 71 OVER UNNAMED STREAM
 FAP RT 311, SECTION 5 BR-1
 LA SALLE COUNTY

SCALE: DATE: 01/13/06

DRAWN BY: CHECKED BY: