


# SUMMARY OF QUANTITIES

CONTRACT NO. 66641				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	06-BHBR	BUREAU	165	4
STA.		TO STA.		
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				**	**	**	**
				1000		X271-2A	
54200649	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT	FOOT	114	114		0	
	PIPE 24"						
54213447	END SECTIONS 12"	EACH	4	4		0	
54213450	END SECTIONS 15"	EACH	4	4		0	
54213459	END SECTIONS 24"	EACH	5	5		0	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2		0	
54246205	INLET BOX, STANDARD 542526	EACH	1	1		0	
54248510	CONCRETE COLLAR	CU YD	2	2		0	
58700300	CONCRETE SEALER	SO FT	1,923	0	1,923		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	176	0	176		
60100945	PIPE DRAINS 12"	FOOT	211	211		0	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	126	0	126		
60624600	CORRUGATED MEDIAN	SO FT	860	860		0	
60625800	ISLAND PAVEMENT (SPECIAL)	SO YD	2,592	2,592		0	
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	4	4		0	
60900515	CONCRETE THRUST BLOCKS	EACH	4	4		0	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	825	825		0	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		0	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		0	
63200310	GUARDRAIL REMOVAL	FOOT	2,612	2,612		0	
63200400	CABLE ROAD GUARD REMOVAL	FOOT	92	92		0	
63600105	CABLE ROAD GUARD, SINGLE STRAND	FOOT	77	77		0	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	125	125		0	
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1.0	1.0	0.0		
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		0	
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	0.0		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0	0.0		
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1.0	1.0	0.0		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	9	9		0	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18		0	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	62	62		0	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27,291	27,291		0	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	375	375		0	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				**	**	**	**
				1000		X271-2A	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,098	1,098		0	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,706	2,706		0	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	576	576		0	
72000100	SIGN PANEL - TYPE 1	SO FT	40	40		0	
72400710	RELOCATE SIGN PANEL - TYPE 1	SO FT	286	286		0	
72400720	RELOCATE SIGN PANEL - TYPE 2	SO FT	15	15		0	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	95	95		0	
73000100	WOOD SIGN SUPPORT	FOOT	654	654		0	
73400100	CONCRETE FOUNDATIONS	CU YD	3	3		0	
73502000	RELOCATE GROUND-MOUNTED SIGN SUPPORT	EACH	4	4		0	
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4	4		0	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	312	312		0	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,064	13,064		0	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	130	130		0	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3,569	3,569		0	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,424	1,424		0	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	172	172		0	
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	574	574		0	
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	132	132		0	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	42	42		0	
78200420	GUARDRAIL MARKERS, TYPE B	EACH	19	19		0	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	33	33		0	
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	2	2		0	
X0322946	REMOVE CONCRETE BOX CULVERT END SECTION	EACH	1	1		0	
X4020500	AGGREGATE SURFACE COURSE, TYPE B 6"	SO YD	56	56		0	
Z0001050	AGGREGATE SUBGRADE 12"	SO YD	4,502	4,502		0	
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		0	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		0	
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	4	4		0	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		0	
Z0032900	LAND SECTION MARKERS	EACH	1	1		0	

 SPECIALTY ITEMS  
 \*\* 10% STATE / 90% FEDERAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
IL ROUTE 89 OVER I-80

## SUMMARY OF QUANTITIES

SCALE: VERT. NONE  
HORIZ. NONE  
DATE: 08/10/07

DRAWN BY ACE/CAD  
CHECKED BY TMH