

### PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (FOOT)	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6" (FOOT)	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8" (FOOT)	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12" (FOOT)	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24" (FOOT)	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS & SYMBOLS (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER BRIDGE (EACH)	SHORT TERM PAVEMENT MARKING (FOOT)
WESTBOUND												
STA. 809+76.00 TO STA. 815+00.00	524			524								
CENTERLINE												
STA. 807+70.00 TO STA. 810+06.00			120	740						6		74
STA. 807+70.00 TO STA. 811+40.00	740											
STA. 810+06.00 TO STA. 811+40.00			20		90					5	3	9
STA. 811+40.00 TO STA. 815+00.00	90											
EASTBOUND												
STA. 807+50.00 TO STA. 808+91.00	910		323			278	64	34	83.2	3		
STA. 809+76.00 TO STA. 815+00.00	524			524								
STAGE 1												
STA. 808+20.00 TO STA. 814+20.00		88										
STAGE 2												
STA. 808+25.00 TO STA. 814+20.00		73										
REMOVAL OF SHORT TERM PAVEMENT MARKING		28										
TOTAL	2,788	189	463	1,788	90	278	64	34	83.2	14	3	83

### PAVEMENT SCHEDULE

LOCATION	SUB-BASE GRANULAR MATERIAL TYPE B (TON)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	PROTECTIVE COAT (SQ YD)	BRIDGE APPROACH PAVEMENT (SQ YD)	BRIDGE APPROACH PAVEMENT (SPECIAL) (SQ YD)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ YD)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (TON)	LEVELING BINDER (MACHINE METHOD) N50 (TON)	COMB. CONC. C & G, TYPE B-6.24 (FOOT)
WESTBOUND											
STA. 808+50.00 TO 810+06.00	17						63	20			
STA. 808+50.00 TO 809+05.00		18	19						42	13	55
STA. 809+05.00 TO 809+70.00		21	22								65
STA. 809+70.00 TO 809+76.00			2			10					6
STA. 809+76.00 TO 810+06.00				56							
STA. 810+06.00 TO 811+40.00			304								
STA. 811+40.00 TO 811+70.00					56						
STA. 811+70.00 TO 811+76.00						8					
STA. 811+76.00 TO 812+15.00		9						12			
STA. 812+15.00 TO 813+00.00		19					119		13		
STA. 811+40.00 TO 813+00.00	25						31	14			
EASTBOUND											
STA. 808+50.00 TO 810+06.00	16							24			
STA. 808+50.00 TO 809+05.00		23	23						16		66
STA. 809+05.00 TO 809+70.00		23	23								65
STA. 809+70.00 TO 809+76.00			2			10			45		6
STA. 809+76.00 TO 810+06.00				56							
STA. 810+06.00 TO 811+40.00			304								
STA. 811+40.00 TO 811+70.00					56						
STA. 811+70.00 TO 811+76.00						8					
STA. 811+76.00 TO 813+00.00		29							19		
STA. 811+40.00 TO 813+00.00	26						137	14			
TOTAL	84	142	699	112	112	36	370	72	99	61	263

### EARTHWORK SCHEDULE

LOCATION	(A)	(B)	(C)	(D)	(E)	FURNISHED EXCAVATION (CU YD)
	TOPSOIL STRIPPING (CU YD)	SUITABLE EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJ FOR 25% SHRINKAGE (CU YD) <small>(B X 0.75)</small>	EMBANKMENT (CU YD)	EARTHWORK BALANCE (+) WASTE (-) SHORTAGE (CU YD) <small>(C - D)</small>	
STAGE 1	64	63	48	192	-144	144
STAGE 2	54	82	62	139	-77	77
TOTALS:	118	145				221

CODE NUMBER	PAY ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	253
20400800	FURNISHED EXCAVATION	CU YD	221

- EARTH EXCAVATION INCLUDES THE QUANTITY OF SUITABLE EARTH EXCAVATION AND TOPSOIL STRIPPING.
- TOPSOIL STRIPPING SHALL BE REUSED FOR VEGETATION SUSTAINING TOPSOIL WHENEVER POSSIBLE.

### PAVEMENT REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	APPROACH SLAB REMOVAL (SQ YD)	COMB. CONC. C & G REMOVAL (FOOT)
WESTBOUND				
STA. 808+50.00 TO 809+05.00		110		
STA. 809+70.00 TO 810+00.00			45	
STA. 811+00.00 TO 811+30.00			41.5	
STA. 811+35.00 TO 811+76.00	56			
STA. 812+15.00 TO 813+00.00		116		
STA. 808+39.00 TO 810+00.00				161
EASTBOUND				
STA. 808+50.00 TO 809+05.00		145		
STA. 809+70.00 TO 810+00.00			45	
STA. 811+00.00 TO 811+30.00			41.5	
STA. 811+35.00 TO 811+76.00	56			
STA. 811+76.00 TO 813+00.00		169		
STA. 808+50.00 TO 810+00.00				150
TOTAL	112	540	173	311

### GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT) (EACH)	GUARDRAIL REMOVAL (FOOT)
WESTBOUND				
STA. 808+62.00 TO 810+06.00	50	1	1	115
STA. 811+40.00 TO 812+59.00	25	1	1	78
EASTBOUND				
STA. 808+87.00 TO 810+06.00	25	1	1	80
STA. 811+40.00 TO 812+72.00	37.5	1	1	153
TOTAL	137.5	4	4	426



200 West Front Street  
Wheaton, IL 60187

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 693 (IL-9)

### SCHEDULE OF QUANTITIES

SCALE: NOT TO SCALE  
DATE: AUGUST 7, 2007

DRAWN BY: MTH  
CHECKED BY: DWB

PLOT SCALE: 1/80  
 PLOT DATE: 8/29/2007  
 PLOT TIME: 5:03:08 PM  
 PLOTTED BY: JTR/coy  
 PLOTTER: HP DesignJet 2400  
 MODEL: 3000