

F.A.P. RYE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	113BR1BR	DEWITT	61	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 2 OF 3

LOCATION OF WORK:

DEWITT COUNTY
RURAL
ROADWAY / STRUCTURE
IMPROVEMENTS
FAP 721 (IL 10)
STA. 238+00
STA. 249+00
80% FEDERAL
20% STATE
X081-2A
QUANTITY

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	QUANTITY
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	723.0
44000400	GUTTER REMOVAL	FOOT	461.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	35.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	295.0
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	12.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50200100	STRUCTURE EXCAVATION	CU YD	282.0
50300100	FLOOR DRAINS	EACH	22.0
50300225	CONCRETE STRUCTURES	CU YD	104.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	242.0
50300260	BRIDGE DECK GROOVING	SQ YD	627.0
50300280	CONCRETE ENCASEMENT	CU YD	7.0
50300300	PROTECTIVE COAT	SQ YD	826.0
50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.	FOOT	1,119.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	62,450.0
50800515	BAR SPLICERS	EACH	64.0
51201610	FURNISHING STEEL PILES HP12X63	FOOT	741.0
51202305	DRIVING PILES	FOOT	741.0
51203610	TEST PILE STEEL HP12X63	EACH	3.0
51500100	NAME PLATES	EACH	1.0
54215547	METAL END SECTIONS 12"	EACH	2.0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	110.0
60100945	PIPE DRAINS 12"	FOOT	71.0
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	163.0
60500060	REMOVING INLETS	EACH	2.0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1.3
60602800	CONCRETE GUTTER, TYPE B	FOOT	348.0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	35.0
60900115	TYPE B INLET BOX, STANDARD 609001	EACH	2.0

PLOT DATE = 8/9/2007
 FILE NAME = C:\p0\projects\6030002\1\B\N\70232\text.dgn
 PLOT SCALE = 43.2355' / IN.
 USER NAME = collierbw

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 721 (IL 10)
SECTION 113BR1BR
DEWITT COUNTY
Sheet 2 of 3

SCALE: NOT TO SCALE
DATE: 07/03/07

DRAWN BY: B.B.P.
CHECKED BY: R.M.N.