

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2(B-5, B-6)	PIKE	112	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				I000 80% FEDERAL 20% STATE BREWSTER	I000 80% FEDERAL 20% STATE BROWN	X028-2A 80% FEDERAL 20% STATE BREWSTER	X081-2A 80% FEDERAL 20% STATE BROWN
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	721	577	144		
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	1957	1118	839		
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	458	254	204		
35800100	PREPARATION OF BASE	SQ YD	674	341	333		
35800200	AGGREGATE BASE REPAIR	TON	4	3	1		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.2	1.2	1		
40600300	AGGREGATE (PRIME COAT)	TON	12	6	6		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	224	100	124		
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1		
40600982	HOT-MIX ASPHALT <sup>SPACE</sup> SURFACE REMOVAL- BUTT JOINT	SQ YD	320	160	160		
40600990	TEMPORARY RAMP	SQ YD	996	68	928		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	242		242		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	442	245	197		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42	36	6		
*	SEE SPECIAL PROVISIONS						

PLOT DATE = 7/26/2007  
 FILE NAME = c:\p\projects\068248\pba\final\sum\_of\_quantities.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = laughlinv1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 SHEET 3 OF 9  
 FAP 304 (IL 96)  
 SECTION 2(B-5, B-6)  
 PIKE COUNTY

SCALE: VERT.  
 DATE:                      HORIZ.

DRAWN BY  
 CHECKED BY