

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2(B-5, B-6)	PIKE	112	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
			I000 80% FEDERAL 20% STATE BREWSTER	I000 80% FEDERAL 20% STATE BROWN	X028-2A 80% FEDERAL 20% STATE BREWSTER	X081-2A 80% FEDERAL 20% STATE BROWN
50300255	CONCRETE SUPERSTRUCTURE	CU YD	88.4			88.4
50300260	BRIDGE DECK GROOVING	SQ YD	212			212
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, ^{36 IN.}	FOOT	327			327
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	32180		9980	22200
50800515	BAR SPLICERS	EACH	331		24	307
51201400	FURNISHING STEEL PILES HP 10X42	FOOT	1822		1250	572
51201610	FURNISHING STEEL PILES HP 12X63	FOOT	1840		1840	
51202305	DRIVING PILES	FOOT	3662		3090	572
51203400	TEST PILE STEEL HP 10X42	EACH	5		4	1
51203610	TEST PILE STEEL HP 12X63	EACH	2		2	
50300280	CONCRETE ENCASEMENT	CU YD	15.4		11.4	4.0
51204650	PILE SHOES	EACH	60		60	
51205200*	TEMPORARY SHEET PILING	SQ FT	1783		1783	
51500100	NAME PLATES	EACH	2		1	1
*	SEE SPECIAL PROVISIONS					

PLOT DATE = 7/21/2007
 FILE NAME = c:\p\pro\pers\682484\pbo\final\sum_of_quantities.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 5 OF 9
FAP 304 (IL 96)
SECTION 2(B-5, B-6)
PIKE COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____

Rev.