CONTRACT NO. 72891

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2(B-5, B-6)	PIKE	112	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SEEDING, FERTILIZING, MULCH

STATION TO STATION	SIDE	SEEDING CLASS 1	SEEDING CLASS 2	NITROGEN FERT NUTR	PHOS FERT NUTR	POTAS FERT NUTR	AGRIC LIME	MULCH METH 2
		ACRE	ACRE	LB	LB	LB	TON	ACRE
BREWSTER CREEK								
FAP 304								
STA 399+80 TO STA 400+18	RT		0.01	1	1	1	0.01	0.01
STA 400+49 TO STA 403+45	RT		0.13	12	12	12	0.26	0.13
STA 403+30 TO STA 403+87	RT		0.07	7	7	7	0.15	0.07
STA 403+99 TO STA 404+44	RT		0.01	1	1	1	0.01	0.01
STA 404+62 TO STA 408+70	RT		0.13	12	12	12	0.27	0.13
STA 399+80 TO STA 401+81	LT	0.04		3	3	3	0.08	0.04
STA 402+20 TO STA 403+27	LT	0.02		2	2	2	0.04	0.02
STA 403+99 TO STA 404+44	LT		0.01	1	1	1	0.02	0.01
STA 404+62 TO STA 405+00	LT		0.01	1	1	1	0.02	0.01
STA 405+00 TO STA 406+44	LT		0.02	1	1	1	0.03	0.02
STA 406+89 TO STA 408+70	LT		0.03	3	3	3	0.06	0.03
BREWSTER CREEK CHANNEL CHANGE STA 299+90 TO STA 302+00	LT/RT		0.06	6	6	6	0.13	0.06
CH 13								
STA 10+39 TO STA 11+46	LT	0.06		5	5	5	0.12	0.06
STA 11+64 TO STA 12+00	LT	0.01		1	1	1	0.02	0.01
STA 10+33 TO STA 12+00	RT		0.01	1	1	1	0.02	0.01
SUBTOTAL		0.13	0.49	56	56	56	1.24	0.62
USE		0.25	0.50	56	56	56	1.5	0.75
BROWN CREEK								
FAP 304								
STA 452+25 TO STA 454+66	RT		0.08	7	7	7	0.16	0.08
STA 454+66 TO STA 8+37.38 (FE)	RT		0.03	3	3	3	0.07	0.03
STA 455+05 TO STA 456+20	RT		0.19	17	17	17	0.38	0.19
STA 456+53 TO STA 461+45	RT		0.31	28	28	28	0.62	0.31
STA 452+25 TO STA 454+86	LT		0.05	5	5	5	0.10	0.05
STA 455+05 TO STA 455+96	LT		0.06	5	5	5	0.12	0.06
STA 455+96 TO STA 456+40	LT		0.01	1	1	1	0.02	0.01
STA 456+45 TO STA 456+73	LT		0.01	1	1	1	0.02	0.01
STA 456+73 TO STA 461+45	LT		0.19	17	17	17	0.39	0.19
SUBTOTAL		0.00	0.94	85	85	85	1.88	0.94
USE		0	1.00	85	85	85	2.0	1.0
TOTAL		0.25	1.50	141	141	141	3.5	1.75

TEMPORARY EROSION CONTROL SEEDING & MULCH, METHOD 2

LOCATION	SEEDING- FOR EROSION CONTROL	MULCH- FOR EROSION CONTROL
	POUND	ACRE
QUANTITIES ARE ESTIMATED		
BREWSTER CREEK		
FAP 304		
VARIOUS LOCATIONS	75.0	0.75
BROWN CREEK		
FAP 304		
VARIOUS LOCATIONS	100.0	1.00
TOTAL	175.0	1.75

PERIMETER EROSION BARRIER

QUANTITIES ARE ESTIMATED		
LOCATION	SIDE	FOOT
BREWSTER CREEK		
FAP 304		
STA 400+99 TO STA 403+46	RT	275
STA 403+56 TO STA 403+87	RT	31
STA 404+59 TO STA 406+00	RT	153
	SUBTOTAL	459
CH 13		
STA 11+19 TO STA 12+00	RT	80
	SUBTOTAL	539
BROWN CREEK		
FAP 304		
STA 454+46 TO STA 454+87	LT	50
STA 454+00 TO STA 454+52	RT	52
STA 454+52 TO STA 455+66	RT	156
STA 455+78 TO STA 456+12	RT	35
STA 456+79 TO STA 461+02	RT	435
	SUBTOTAL	728
TOTAL		1267

PRIME COAT/AGGREGATE PRIME COAT

LOCATION	BIT MATL (PRIME CT)	AGGREGATE (PRIME CT)
	TON	TON
BREWSTER CREEK		
FAP 304		
STA 399+80.00 TO STA 408+70.00	1.0	4.8
CH 13		
STA 10+12.20 TO STA 12+00.00	0.2	1.0
SUBTOTAL	1.2	5.8
USE	1.2	6.0
BROWN CREEK		
FAP 304		
STA 452+25.00 TO STA 455+76.50	0.4	2.0
STA 456+92.50 TO STA 461+45.00	0.5	3.0
TR 96		
STA 10+12.00 TO STA 10+60.19	0.1	0.4
SUBTOTAL	1.0	5.4
USE	1.0	6.0
TOTAL	2.2	12.0

TEMPORARY RAMP

LOCATION	DEPTH	LENGTH	WIDTH	TEMP RAMP
	INCH	FOOT	FOOT	SQ YD
BREWSTER CREEK				
FAP 304				
STA 399+80.00 TO STA 399+85.00	1.50	5.00	24.0	11.1
STA 408+65.00 TO STA 408+70.00	1.50	5.00	24.0	11.1
LT - STA 403+00.00 TO STA 404+00.00 (CH13)	0.75	5.00	81.0	45.0
SUBTOTAL				67.2
USE				68
BROWN CREEK				
FAP 304				
STA 452+25.00 TO STA 452+30.00	1.50	5.00	24.0	11.1
STA 461+40.00 TO STA 461+45.00	1.50	5.00	24.0	11.1
STA 455+26.50 TO STA 455+76.50 - STAGE II	4.50	50.00	16.0	200.0
STA 456+92.50 TO STA 457+50.00 - STAGE II	10.00	57.50	20.0	230.0
STA 455+26.50 TO STA 455+76.50 - STAGE III	4.50	50.00	16.0	200.0
STA 456+92.50 TO STA 457+50.00 - STAGE III	10.00	57.50	20.0	230.0
LT - STA 454+46.00 TO STA 455+36.00 (TR96)	0.75	5.00	81.0	45.0
SUBTOTAL				927.2
USE				928
TOTAL				996

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITITES

SHEET 2 OF 9
FAP 304 (IL 96)
SECTION 2(B-5,B-6)
PIKE COUNTY

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 7/31/2007
FILE NAME = c:\Projects\d652484\pabs_final\schedules.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = bengtlirc