

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2(B-5, B-6)	PIKE	112	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STEEL PLATE BEAM GUARDRAIL REMOVAL

LOCATION	SIDE	QUANTITY (FOOT)
BREWSTER CREEK		
FAP 304		
STA 403+37.2 TO STA 403+89.9	RT	52.6
STA 404+21.9 TO STA 404+99.5	RT	77.6
STA 404+21.9 TO STA 405+74.6	LT	152.7
CH 13		
STA 10+26.0 TO STA 10+62.8	RT	40.8
SUBTOTAL		323.7
BROWN CREEK		
FAP 304		
STA 455+66.3 TO STA 456+19.0	RT	52.7
STA 455+41.2 TO STA 456+19.0	LT	77.8
STA 456+51.1 TO STA 457+53.7	LT	102.6
STA 456+51.1 TO STA 457+28.8	RT	77.7
SUBTOTAL		310.8
TOTAL		634.5

TEMPORARY CONCRETE BARRIERS

TEMPORARY CONCRETE BARRIERS LOCATION	ACTIVE LANE	QUANTITY (FOOT)	TEMPORARY CONCRETE BARRIERS RELOCATE TO	ACTIVE LANE	QUANTITY (FOOT)
BREWSTER CREEK					
FAP 304					
STA 402+37.50 TO STA 406+12.50 - STAGE II	RT	375	STA 401+87.50 TO STA 406+62.50 - STAGE III	LT	375
STA 401+87.50 TO STA 406+62.50 - STAGE III	LT	100			
SUBTOTAL		475	SUBTOTAL		375
BROWN CREEK					
FAP 304					
STA 454+37.50 TO STA 458+25.00 - STAGE II	LT	387.5	STA 454+00.00 TO STA 458+62.50 - STAGE III	RT	387.5
STA 454+00.00 TO STA 458+62.50 - STAGE III	RT	75			
SUBTOTAL		462.5	SUBTOTAL		387.5
USE		938	USE		763

FURNISHING AND ERECTING RIGHT OF WAY MARKERS

LOCATION	OFFSET (FT)		METHOD A	METHOD B
	LT	RT	EACH	EACH
BREWSTER CREEK				
FAP 304				
STA 402+00.00		40.58	1	
STA 403+00.00		60.00	1	
STA 405+00.00		60.00	1	
STA 406+00.00		40.34	1	
STA 403+12.59	39.20			1
STA 405+00.00	39.43		1	
CH 13				
STA 11+44.55	40.00			1
STA 11+52.04		49.30	1	
STA 11+88.52	40.00			1
STA 12+40.35	17.95			1
SUBTOTAL			6	4
BROWN CREEK				
FAP 304				
STA 454+50.00		40.00		1
STA 455+04.72		94.72	1	
STA 455+50.00		140.00	1	
STA 456+00.00		140.00	1	
STA 456+00.00		50.00		1
STA 456+53.82		50.00		1
STA 460+00.00		50.00		1
STA 460+88.90		45.00		1
STA 454+42.88	40.00		1	
STA 454+74.15	64.20		1	
STA 455+16.97	70.00		1	
STA 460+50.00	70.00		1	
STA 460+88.90	40.00		1	
SUBTOTAL			8	5
TOTAL			14	9

GEOTEXTILE RETAINING WALL

STATION	SIDE	DEPTH FROM FACE (FEET)	EMBEDMENT (FEET)	HEIGHT (FEET)	WIDTH (FEET)	REINFORCEMENT SPACING (FEET)	SO FT
BREWSTER CREEK							
FAP 304							
STA 403+91.00 TO STA 403+98.83	2.5' LT	9.8	3	10	8	1	80
STA 403+91.00 TO STA 403+98.83	2.5' LT	9.8	3	3	11	1	33
STA 403+98.83 TO STA 404+43.17	2.5' LT	9.8	3	1.4	45	1.4	63
TOTAL							176
USE							176

GUARDRAIL MARKERS, TYPE A

LOCATION	SIDE	SPACING	QUANTITY (EACH)
BREWSTER CREEK			
STA 11+17.90 (CH 13 - RT) TO STA 406+00.00 (FAP 304)			
STA 403+37.50 TO STA 406+00.00	RT	71.8	5
SUBTOTAL			10
BROWN CREEK			
STA 455+25.87 TO STA 456+09.00	LT	63.1	2
STA 455+25.87 TO STA 456+09.00	RT	63.1	2
STA 456+60.00 TO STA 459+18.13	RT	79.4	4
STA 456+60.00 TO STA 460+68.13	LT	77.6	6
SUBTOTAL			14
TOTAL			24

TERMINAL MARKER - DIRECT APPLIED

LOCATION	SIDE	QUANTITY EACH
BREWSTER CREEK		
FAP 304		
STA 11+17.90 (CH 13)	RT	1
STA 406+00.00	LT	1
STA 403+37.50	RT	1
STA 406+62.50	RT	1
SUBTOTAL		4
BROWN CREEK		
STA 455+25.87	RT	1
STA 455+25.87	LT	1
STA 459+18.13	RT	1
STA 460+68.13	LT	1
SUBTOTAL		4
TOTAL		8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 SHEET 5 OF 9  
 FAP 304 (IL 96)  
 SECTION 2(B-5, B-6)  
 PIKE COUNTY

SCALE: VERT.  
 HORIZ.  
 DATE

DRAWN BY  
 CHECKED BY