

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2(B-5, B-6)	PIKE	112	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVEMENT MARKING

STATION TO STATION	SIDE	TYPE	DISTANCE (FT)	5" YELLOW (FT)	5" WHITE (FT)	24" WHITE (FT)	PAV MARK REMVL (SQ FT)	WORK ZONE PAV MARK REMVL (SQ FT)	REFLECTIVE MARKER 2-WAY AMBER (EACH)	SHORT TERM PAVMNT MARKING		TEMP PAVMNT MRKING LINE		
										YELLOW	WHITE	5" (FT)	24" (FT)	
BREWSTER CREEK														
FAP 304														
STA 400+05 TO STA 408+45	10' RT	EXIST EDGE LINE	840				353							
STA 400+05 TO STA 401+14	CL	CL - SOLID/SKIP-DASH	109				59							
STA 401+14 TO STA 403+00	CL	CL - SOLID/SOLID	186				155							
STA 405+27 TO STA 408+45	CL	CL - SOLID/SKIP-DASH	318				168							
STA 399+80 TO STA 408+70	CL	REFLECTOR	80' SPACING						11					
STA 400+05 TO STA 408+45	RT	5" TEMP LINE (WHITE)	840' STAGE II					353				840		
STA 400+05 TO STA 408+45	VARIABLES	5" TEMP LINE (WHITE)	840' STAGE II					353				840		
STA 400+05 TO STA 408+45	LT	5" TEMP LINE (WHITE)	840' STAGE III					353				840		
STA 400+05 TO STA 408+45	VARIABLES	5" TEMP LINE (WHITE)	840' STAGE III					353				840		
STA 399+80 TO STA 408+70	11' RT	5" EDGE LINE	890		890									
STA 399+80 TO STA 403+00	11' LT	5" EDGE LINE	320		320									
STA 404+00 TO STA 408+70	11' LT	5" EDGE LINE	370		370									
STA 399+80 TO STA 401+14	CL	CL - SOLID/SKIP-DASH	134	174										
STA 401+14 TO STA 405+27	CL	CL - SOLID/SOLID	413	826										
STA 405+27 TO STA 408+70	CL	CL - SKIP-DASH/SOLID	343	433										
STA 400+05	0 TO 12' RT	TEMP STOP BAR	12' STAGE II										12	
STA 408+25	0 TO 12' LT	TEMP STOP BAR	12' STAGE II										12	
STA 399+80 TO STA 408+70	CL	4' / 40' SKIP-DASH	AFTER LEV BINDER							88				
STA 399+80 TO STA 408+70	CL	4' / 40' SKIP-DASH	AFTER FINAL SURFACE				37			88				
CH 13														
STA 10+45	0 TO 11' LT	TEMP STOP BAR	11										11	
STA 10+45	0 TO 11' LT	STOP BAR	11											
SUBTOTAL					1433	1580	11	735	1449	11	176	0	3360	35
BROWN CREEK														
FAP 304														
STA 452+25 TO STA 461+00	11' LT	EXIST EDGE LINE	875				368							
STA 452+25 TO STA 455+00	CL	CL - SKIP-DASH/SOLID	300				160							
STA 457+50 TO STA 460+50	CL	CL - SKIP-DASH/SOLID	300				160							
STA 452+25 TO STA 461+45	CL	REFLECTOR	80' SPACING						13					
SRA 452+25 TO STA 460+50	LT	5" TEMP LINE (WHITE)	825' STAGE II					347				825		
SRA 452+25 TO STA 460+50	VARIABLES	5" TEMP LINE (WHITE)	825' STAGE II					347				825		
SRA 452+25 TO STA 460+50	RT	5" TEMP LINE (WHITE)	825' STAGE III					347				825		
SRA 452+25 TO STA 460+50	VARIABLES	5" TEMP LINE (WHITE)	825' STAGE III					347				825		
STA 452+25 TO STA 461+45	CL	CL - SKIP-DASH/SOLID	920	1160										
STA 452+25 TO STA 454+43	11' LT	5" EDGE LINE	218		218									
STA 454+43 TO STA 461+45	11' LT	5" EDGE LINE	702		702									
STA 452+25 TO STA 461+45	11' RT	5" EDGE LINE	920		920									
STA 452+25	0 TO 12' RT	TEMP STOP BAR	12										12	
STA 460+50	0 TO 12' LT	TEMP STOP BAR	12										12	
STA 452+25 TO STA 461+45	CL	4' / 40' SKIP-DASH	AFTER LEV BINDER							92				
STA 452+25 TO STA 461+45	CL	4' / 40' SKIP-DASH	AFTER FINAL SURFACE				37			92				
TR 96														
STA 10+36	0 TO 14' LT	TEMP STOP BAR	14										14	
STA 10+36	0 TO 14' LT	STOP BAR	14			14								
SUBTOTAL					1160	1840	14	688	1425	13	184	0	3300	38
TOTALS					2593	3420	25	1423	2874	24	360	0	6660	73

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SHEET 8 OF 9
 FAP 304 (IL 96)
 SECTION 2(B-5, B-6)
 PIKE COUNTY
 SCALE: VERT. / HORIZ.
 DATE: / / DRAWN BY: / CHECKED BY: /

PLOT DATE = 7/31/2007
 FILE NAME = c:\p\projects\652484\paba_r.mol\schedule.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1