

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	3B-1	PIKE	51	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	CONSTRUCTION CODE
				ROADWAY FAP 304 80% FED 20% STATE 1000-2A	STRUCTURE SN 075-2506 80% FED 20% STATE X02B-2A
40600300	AGGREGATE (PRIME COAT)	TON	5	5	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	111	111	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	302	302	
40600990	TEMPORARY RAMP	SQ YD	27	27	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	222	222	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	113	113	
44000100	PAVEMENT REMOVAL	SQ YD	140	140	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	55	55	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	136	136	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	278	278	
50800105	REINFORCEMENT BARS	<i>POUND</i>	67480		67480
50800205	REINFORCEMENT BARS, EPOXY COATED	<i>POUND</i>	1430		1430
50800515	BAR SPLICERS	EACH	179		179
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	419		419
54201480	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	239	239	
54201495	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"	FOOT	175	175	
54215565	METAL END SECTIONS 30"	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	427	427	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9	
66700205	PERMANENT SURVEY MARKERS TYPE 1	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

PLOT DATE = Aug-31-2007 11:42:16AM  
 FILE NAME = e:\projects\653784\upchurch\mes\sumquant.mht  
 PLOT SCALE = 42.3029 / IN.  
 USER NAME = laughlin

**The Upchurch Group**  
 HILLSIDE, IL. (708) 448-2821  
 MATTOON, IL. (217) 285-3177

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
  
**SUMMARY OF QUANTITIES**  
**IL 96 OVER JIMTOWN BRANCH**  
**FAP 304 SECTION 3B-1**  
**PIKE COUNTY**  
  
 SCALE: \_\_\_\_\_ DRAWN BY SJF  
 DATE: \$DATE CHECKED BY MJS