CONTRACT NO. 72908

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	3B-1	PIKE	51	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIDE ROADS AND ENTRANCE IMPROVEMENT SCHEDULE

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ HMA SHLD TO LIMITS OF IMPROVEMENT)	PR HMA THICKNESS	HMA SURF. REM. - BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE BASE COURSE TY - A	AGGREGATE BASE COURSE TY - B	BIT (P.C.)	INCIDENTAL HMA SURF.
(LT / RT) STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / BIT. / P.C.C.)	FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON
ENTRANCES														
LT 782+55	FE	AGG	24			27.5	-	-	-	-	-	41	-	-
RT 783+85	FE	AGG	22			63.7	-	-	-	-	-	57	-	-
LT 785+55	PE	AGG	32			35.8	3.5	-	43	-	-	48	-	8
LT 787+26	PE	AGG	24			37	3.5	-	37	-	-	39	-	7
LT 789+15	PE	BIT	14			26	3.5	40	65	-	-	21	-	13
LT 790+37	PE	BIT	16			28.5	3.5	41	76	-	-	24	-	15
LT 791+86	PE	BIT	16			28.7	3.5	61	76	-	-	24	-	15
SIDE ROADS														
LT 784+00	SR	O&C	24			184.40	2 *	-	-	-	-	-	-	55 *
TOTAL ENTRANCES & SIDE ROADS:								142	297			253		113

NOTE: * 8" HMA BASE COURSE PAID FOR SEPARATELY.

PAVING SCHEDULE

LOCATION	HMA BASE COURSE WIDENING 10"	LEVELING BINDER (MACHINE METHOD)	HMA BASE COURSE 10"	HMA BASE COURSE 8"	HMA SURFACE COURSE	HMA SHOULDERS
780+05 RT TO 789+95 RT		55.5 TONS			111 TONS	
780+05 LT TO 789+95 LT		55.5 TONS			111 TONS	
780+50 RT TO 789+36.50 RT	41 SY		849 SY			110 TONS
782+00 LT TO 787+48.7 LT	224 SY					26 TONS
784+37 RT TO 785+15 RT			139 SY			
784+37 LT TO 785+15 LT			104 SY			
10+12 TO 11+50				447 SY		
TOTAL:	265 SY	111 TONS	1092 SY	447 SY	222 TONS	136 TONS

44000100

PAVEMENT REMOVAL

STATION	TO	STATION	AREA (SQ YD)
784+37		785+15	140

70300230

TEMPORARY PAVEMENT MARKING LINE 5"

STATION	TO	STATION	COLOR	LENGTH (FEET)
780+05		789+95	YELLOW	990
782+80		785+20	YELLOW	240
780+05 RT		789+95 RT	WHITE	990
780+05 LT		783+50 LT	WHITE	345
784+80 LT		789+95 LT	WHITE	515
			TOTAL LENGTH:	3080

70300100

SHORT TERM PAVEMENT MARKING

STATION	TO	STATION	COLOR	LENGTH (FEET)
782+05		789+95	YELLOW	180
			TOTAL FOR 2 APPLICATIONS:	180

78001120

PAINT PAVEMENT MARKING-LINE 5"

STATION	TO	STATION	COLOR	LENGTH (FEET)
780+05		789+95	YELLOW	990
782+80		785+20	YELLOW	240
780+05 RT		789+95 RT	WHITE	990
780+05 LT		783+50 LT	WHITE	345
784+80 LT		789+95 LT	WHITE	515
			TOTAL LENGTH:	3080

70301000

WORK ZONE PAVEMENT MARKING REMOVAL

STATION	TO	STATION	COLOR	AREA (SQ FT)
780+05		789+95	YELLOW	30
			TOTAL AREA:	30

The Upchurch Group
HILLSIDE, IL. (708) 449-2321
MATTOON, IL. (217) 235-3177

PLOT DATE = Aug-31-2007 11:48:06AM
FILE NAME = c:\projects\d653704\upchurch_final\schedule.sht
PLOT SCALE = 42.2857 ' / IN.
USER NAME = Laughlin-J

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL 96 OVER JIMTOWN BRANCH
FAP 304 SECTION 3B-1
PIKE COUNTY

SCALE: DRAWN BY SJF
DATE: $DATE CHECKED BY MJS