

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
751	101B-2	PIKE	48	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SEEDING SCHEDULE						
LOCATION	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHER. FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRIC. GROUND LIMESTONE	MULCH METHOD 2
	ACRE	POUND	POUND	POUND	TON	ACRE
NORTHWEST QUADRANT	0.2	18	18	18	0.4	0.2
NORTHEAST QUADRANT	0.3	27	27	27	0.6	0.3
SOUTHWEST QUADRANT	0.2	18	18	18	0.4	0.2
SOUTHEAST QUADRANT	0.4	36	36	36	0.8	0.4
TOTAL	1.1	99	99	99	2.2	1.1

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
LOCATION	OFFSET	MARKER
		EACH
STA 377+00.00	40.00' RT	1
STA 378+50.00	40.00' LT	1
STA 380+00.00	90.00' RT	1
STA 380+00.01	90.00' LT	1
STA 381+50.00	100.00' LT	1
STA 382+50.00	40.00' LT	1
STA 385+50.00	90.00' RT	1
STA 386+00.00	40.46' RT	1
TOTAL		8

PAVEMENT MARKING				
LOCATION	RAISED REFL PVT MK REMOVAL	PAINT PVT MK - LINE 5" SOLID WHITE	PAINT PVT MK - LINE 5" SD YELLOW	RAISED REFL PVT MARKERS
	EACH	FOOT	FOOT	EACH
STA 377+00.00 TO STA 385+00.00 (PERMANENT)	11	1600	200	11
TOTAL =	11	1600	200	11

EARTHWORK				
	EARTH EXCAVATION (CU. YD.)	EARTH EXC. ADJ FOR SHRINKAGE (CU. YD.)	EMBANKMENT (CU. YD.)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU. YD.)
	TOTAL	2750	2063	1847

RIPRAP SCHEDULE		
LOCATION	STONE RIPRAP CLASS A5	FILTER FABRIC
	SQ YD	SQ YD
LT STA 380+38.9 TO LT STA 381+70.4	1213.1	1213.1
RT STA 380+36.2 TO RT STA 381+61.1	1036.2	1036.2
TOTAL =	2249.3	2249.3

AGGREGATE SHOULDERS			
LOCATION	LENGTH	AVE WIDTH	AGGREGATE SHOULDERS
			TYPE B
	FOOT	FOOT	TON
LT STA 377+00.00 TO LT STA 378+50.00	148.60	3.00	4.23
RT STA 377+00.00 TO RT STA 378+50.00	148.60	3.00	4.23
LT STA 378+50.00 TO LT STA 379+56.02	106.02	3.00	13.89
RT STA 378+50.00 TO RT STA 379+56.02	106.02	3.00	13.89
LT STA 379+56.02 TO LT STA 380+00.00	43.98	3.00	5.76
RT STA 379+56.02 TO RT STA 380+00.00	43.98	3.00	5.76
LT STA 380+00.00 TO LT STA 380+31.50	31.50	3.00	4.13
RT STA 380+00.00 TO RT STA 380+31.50	31.50	3.00	4.13
LT STA 381+68.50 TO LT STA 381+80.00	11.50	3.00	1.51
RT STA 381+68.50 TO RT STA 381+80.00	11.50	3.00	1.51
LT STA 381+80.00 TO LT STA 382+45.50	65.50	3.00	8.58
RT STA 381+80.00 TO RT STA 382+45.50	65.50	3.00	8.58
LT STA 382+45.50 TO LT STA 383+50.00	104.50	3.00	13.69
RT STA 382+45.50 TO RT STA 383+50.00	104.50	3.00	13.69
LT STA 384+53.60 TO LT STA 385+00.00	148.60	3.00	4.23
RT STA 383+50.00 TO RT STA 385+00.00	148.60	3.00	4.23
TOTAL =			112.01

SCHEDULE FOR REMOVING EXISTING CULVERT	
LOCATION	CULVERT REMOVAL 12"
	FOOT
RT STA 382+71.0	48
TOTAL =	48

TREE REMOVAL	
LOCATION	TREE REMOVAL > 15"
	UNIT
LT STA 379+50	36
TOTAL =	36

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. / HORIZ. DATE

DRAWN BY / CHECKED BY