

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	142BR-4	SANGAMON	24	3

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

SUMMARY OF QUANTITIES

PAY CODE	ITEM	UNITS	SN 084-0176 80% FEDERAL 20% STATE CONSTRUCTION CODE X080-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5
40600300	AGGREGATE (PRIME COAT)	TON	3
40600590	TEMPORARY RAMP	SQ YD	157
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NS0	TON	94
42001300	PROTECTIVE COAT	SQ YD	1105
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1110
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	31.4
50300225	CONCRETE STRUCTURES	CU YD	28.0
50300260	BRIDGE DECK GROOVING	SQ YD	1056
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	8945
50500495	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	30000
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16670
50800515	BAR SPLICERS	EACH	223
50901050	STEEL RAILING, TYPE SM	FOOT	462
51500100	NAME PLATES	EACH	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	96
50000190	CONTROLLED LOW-STRENGTH MATERIAL	CUM YD	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	162.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	486
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	37.5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10
67100100	MOBILIZATION	LSUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1
70106500	TEMPORARY BRIDGE, TRAFFIC SIGNALS	EACH	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	224
70300630	TEMPORARY PAINT PAVEMENT MARKING - LINE 5"	FOOT	1587
70301030	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	737

PAY CODE	ITEM	UNITS	SN 084-0176 80% FEDERAL 20% STATE CONSTRUCTION CODE X080-2A
70400100	TEMPORARY CONCRETE BARRIER	FOOT	519
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	444
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	1587
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12
* 78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	3
78300105	PAVEMENT MARKING REMOVAL	FOOT	1227
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4
X8030305	CONCRETE WEARING SURFACE, 5"	SQ YD	1105
X7200201	WIDTH RESTRICTION SIGNING	LSUM	1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	96
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030280	IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEMS

PLAN	DATE
BY	
REVISIONS	
PLOTTED	
CHECKED	
DATE	
NOTE BOOK	
NO.	

PROFILE	DATE
BY	
REVISIONS	
PLOTTED	
CHECKED	
DATE	
NOTE BOOK	
NO.	

PLOT DATE : Aug 10 2007 07:49:04AM
 PLOT SCALE : 4:1
 USER NAME : laughtinr1

K+ K-Plus Engineering, Ltd.
 753 WINDSOR ROAD
 CHARLESTON, IL 61920
 (217) 348-1900
 WWW.K-PLUSENGINEERING.LTD.COM
 ILLINOIS DEPARTMENT OF PROFESSIONAL REGULATION REGISTRATION #104-003605

** THIS DOCUMENT IS THE PROPERTY OF K-PLUS ENGINEERING, LTD. AND NO PART HEREIN SHALL BE USED **
 EXCEPT FOR THIS SPECIFIC PROJECT WITHOUT THE WRITTEN CONSENT OF K-PLUS ENGINEERING, LTD.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES

FAP 753 (IL RTE. 104)
 OVER HORSE CREEK
 SECTION 142BR-4
 SANGAMON COUNTY

DATE: 08-01-07

DRAWN BY: ADG
 CHECKED BY: DC