CONTRACT NO. 72B08

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
735	*	MACOUPIN	4	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 6RS-4; 7RS-7

2

Station Range			Width (FT)	Length (FT)	Area (SY)	CAPE Seal (SY)	~~Aggregate (Prime) (TONS)~~	~~Bituminous (Prime) (TONS)~~	Raised Reflective Markers Removal (EACH)	Raised Reflective Markers Installation (EACH)
72+34.	TO	171+86.7	20	9,953	22,117	22,117	~~44.2~~	~~8.4~~	124	124
173+60.	TO	252+91.	20	7,931	17,624	17,624	~~35.2~~	~~6.7~~	99	99
399+75.	TO	558+58.	20	15,883	35,296	35,296	~~70.6~~	~~13.4~~	199	199
			Totals	*33,767*	*75,037*	*75,037*	~~*150*~~	~~*28.5*~~	*422*	*422*
				6.395 mi						

2

Paint Pavement Marking Line, 5"

Location	Length (FT)	Edge Line (FT)	Center Dash (FT)	Center Solid (FT)
Passing Zone	13,507	27,013	3,377	0
No Passing - One Way	8,442	16,883	2,110	8,442
No Passing Zones	11,818	23,637	0	23,637
	sub-Totals	67,533	5,487	32,078
	Total	*105,099*		

Notes:

The Fine Aggregate used with the A-1 treatment for the CAPE seal shall be CA-16.
For Plan Circulation, assume 35% of length will be No-Passing zones, 25% No-Passing one way.

2 Rev. 11-7-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 735
SECTION 6RS-4; 7RS-7
MACOUPIN COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Aug-13-2007 01:49:18PM
FILE NAME = c:\Projects\d6531507\sht-soq.dgn
PLOT SCALE = 105.8024 ' / IN.
USER NAME = leughlinrl