CONTRACT NO. 74092

| S.B.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 15B | (17C)B | WAYNE | 17 | 3 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | 100% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|---|---|---|---|---|---|---|
| | | | | X028-2A | | |
| 20200100 | EARTH EXCAVATION | CU YD | 15 | 15 | | |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 100 | 100 | | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 105 | 105 | | |
| 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 250 | 250 | | |
| 25001000 | SEEDING, CLASS 2 (SPECIAL) | ACRE | 0.1 | 0.1 | | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 299 | 299 | | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 386 | 386 | | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 94 | 94 | | |
| 28200200 | FILTER FABRIC | SQ YD | 142 | 142 | | |
| 31101000 | SUB-BASE GRANULAR MATERIAL, TYPE B | TON | 34 | 34 | | |
| 42000500 | PORTLAND CEMENT CONCRETE PAVEMENT 10" | SQ YD | 139 | 139 | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 60 | 60 | | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 86 | 86 | | |
| 50100100 | REMOVAL OF EXISTING STRUCTURES | EACH | 1 | 1 | | |
| 51500100 | NAME PLATES | EACH | 1 | 1 | | |
| 54000900 | BOX CULVERT END SECTIONS, SPECIAL | EACH | 2 | 2 | | |
| 54011009 | PRECAST CONCRETE BOX CULVERT 10' X 9' | FOOT | 62 | 62 | | |
| * 63000025 | STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES | FOOT | 50 | 50 | | |
| * 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH | 4 | 4 | | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 164 | 164 | | |
| 67000500 | ENGINEER'S FIELD OFFICE, TYPE B | CAL MO | 4 | 4 | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | L SUM | 1 | 1 | | |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 124 | 124 | | |
| * 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 8 | 8 | | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | | |
| * Z0054505 | ROCK FILL (REPLACEMENT) | TON | 240 | 240 | | |

* SPECIALTY ITEMS

Rev.

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 6/24/2007
FILE NAME = c:\projects\74092d\shtsoq_74092.dgn
PLOT SCALE = 20.0000 ' / IN.
USER NAME = staffernek