

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	44	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

• D7 SAFETY 2008-2

## GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF ERECTING GUARDRAIL, PLACING EMBANKMENT, CONSTRUCTING IMPACT ATTENUATORS, CONSTRUCTING PIPE CULVERTS, INLETS, EXTENDING PIPE UNDERDRAINS (SPECIAL), AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

ALL ELEVATIONS SHOWN IN PLANS ARE BASED ON U. S. G. S. DATUM.

ALL DISTURBED AREAS WITHIN THE CONSTRUCTION LIMITS SHALL BE FERTILIZED AND SEEDED. SEEDING SHALL BE CLASS 2 IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND THE APPLICABLE ARTICLES OF SECTION 250 OF THE STANDARD SPECIFICATIONS.

## INDEX OF SHEETS

- 1 Cover Sheet
- 2 Index of Sheets, Standards, General Notes
- 3 Summary of Quantities
- 4 County Locations Map
- 5 Typical Sections
- 6-9 Schedule of Quantities
- 10-13 Plan and Profile Sheets
- 14-15 Details
- 16-44 Cross Sections
- 44A. TRAFFIC BARRIER TERM. TY 2 DETAIL

## STANDARDS IN THE PLANS

- 000001-04 Standard Symbol, Abbreviations and Patterns
- 001001-01 Areas of Reinforcement Bars
- 001006 Decimal of an Inch and of a Foot
- 280001-03 Temporary Erosion Control Systems
- 542531-02 Inlet Box Type G, 600mm (24")
- 542601 Reinforced Concrete Pipe Elbow
- 542606 Reinforced Concrete Pipe Tee
- 601001-01 Sub-Surface Drains
- 601101 Concrete Headwall for Pipe Drain
- 602601-01 Precast Reinforced Concrete Flat Slab Top
- 604036-01 Grate, Type B
- 630001-07 Steel Plate Beam Guardrail
- 630301-04 Shoulder Widening for Type 1 (Special) Guardrail Terminals
- 631011-03 Traffic Barrier Terminal, Type 2
- 635006-02 Reflector and Terminal Marker Placement
- 635011-01 Reflector Marker and Mounting Details
- 701011-01 Off-Road Operations, Multilane, 4.5m (15') to 600mm (24") from Pavement Edge
- 701101-01 Off-Road Operations, Multilane, More Than 4.5m (15') Away
- 701400-02 Approach to Lane Closure, Freeway/Expressway
- 701406-04 Lane Closure, Freeway/Expressway, Day Operations Only
- 702001-06 Traffic Control Devices

PLOT DATE = 8/19/2008  
 FILE NAME = c:\projects\74249\htcover-74249.dgn  
 PLOT SCALE = 50.0000 / 1 IN.  
 USER NAME = svt-1234

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**GENERAL NOTES,  
 INDEX OF SHEETS  
 AND STANDARDS**  
 SCALE: VERT. \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_

Rev.