

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	44	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\* D7 SAFETY 2008-2

TRAFFIC BARRIER TERMINAL TYPE 1,  
SPECIAL (TANGENT)

LOCATION	STATION	TO	STATION	EA.
Effingham County				
*RT I-57/FAYETTE AVE.	2132+26.40		2131+76.40	1.0
RT MED SHLDR	2130+86.69		2131+36.69	1.0
LT MED SHLDR	2138+13.67		2138+63.67	1.0
RT MED SHLDR	2155+06.35		2155+56.35	1.0
LT MED SHLDR	2162+20.75		2162+70.75	1.0
RT MED SHLDR	2212+31.33		2212+81.33	1.0
LT MED SHLDR	2219+46.25		2219+96.25	1.0
*LT SHOULDER	2218+53.24		2219+03.24	1.0
*RT SHOULDER	2246+05.92		2246+55.92	1.0
RT MED SHLDR	2255+17.11		2255+67.11	1.0
LT MED SHLDR	2262+31.64		2262+81.64	1.0
RT MED SHLDR	2296+63.04		2297+13.04	1.0
LT MED SHLDR	2303+77.39		2304+27.39	1.0
*RT SHOULDER	2330+55.61		2331+05.61	1.0
*LT I-57/US 45 RAMP	32+21.08		32+71.08	1.0
RT MED SHLDR	2329+67.50		2330+17.50	1.0
LT MED SHLDR	2336+81.87		2337+31.87	1.0
*RT SHOULDER	2355+53.41		2356+03.41	1.0
RT MED SHLDR	2355+53.59		2356+03.59	1.0
*LT MED SHLDR	5383+88.64		5384+38.64	1.0
*LT SHOULDER	5384+40.76		5383+90.76	1.0
*LT SHOULDER	5409+46.70		5409+96.70	1.0
*RT MED SHLDR	5403+95.59		5404+45.59	1.0
*LT MED SHLDR	5409+46.10		5409+96.10	1.0
*LT SHOULDER	5436+41.60		5436+91.60	1.0
*RT MED SHLDR	5430+97.00		5431+47.00	1.0
*LT MED SHLDR	5436+41.60		5436+91.60	1.0
Coles County				
NB EXIT 57/45	1+89.80		2+39.80	1.0
SB EXIT 57/45	2+02.43		2+52.43	1.0

TOTAL = 29.0

NOTE: (\*) DENOTES LOCATIONS WHERE SHOULDER WIDENING IS TO BE CONSTRUCTED.

TRAFFIC BARRIER TERMINAL, TYPE 2

LOCATION	STATION	TO	STATION	EA.
Effingham County				
RT SHOULDER	2134+13.90		2134+26.4	1.0
RT MED SHLDR	2134+24.19		2134+36.69	1.0
LT MED SHLDR	2135+26.17		2135+38.67	1.0
RT MED SHLDR	2158+31.35		2158+43.85	1.0
LT MED SHLDR	2159+33.25		2159+45.75	1.0
LT SHOULDER	2159+29.51		2159+42.01	1.0
RT MED SHLDR	2215+56.33		2215+68.83	1.0
LT MED SHLDR	2216+58.75		2216+71.25	1.0
LT SHOULDER	2216+53.24		2216+65.74	1.0
RT SHOULDER	2248+43.42		2248+55.92	1.0
RT MED SHLDR	2258+42.11		2258+54.61	1.0
LT MED SHLDR	2262+31.64		2262+81.64	1.0
RT MED SHLDR	2299+88.04		2300+00.54	1.0
LT MED SHLDR	2300+89.89		2301+02.39	1.0
LT I-57/US 45 RAMP	30+58.58		30+71.08	1.0
RT SHOULDER	2333+05.61		2333+18.11	1.0
RT MED SHLDR	2332+92.50		2333+05.00	1.0
LT MED SHLDR	2333+94.37		2334+06.87	1.0
RT SHOULDER	2358+03.41		2358+15.91	1.0
RT MED SHLDR	2357+91.09		2358+03.39	1.0
LT SHOULDER	5381+78.26		5381+90.76	1.0
LT SHOULDER	5407+34.50		5407+46.70	1.0
RT MED SHLDR	5406+45.59		5406+58.09	1.0
LT MED SHLDR	5407+33.60		5407+46.10	1.0
LT SHOULDER	5434+29.10		5434+41.60	1.0
RT MED SHLDR	5433+47.00		5433+59.50	1.0
LT MED SHLDR	5434+29.10		5434+41.60	1.0
Coles County				
NB EXIT 57/45	3+77.30		3+89.80	1.0
SB EXIT 57/45	4+14.93		4+27.43	1.0

TOTAL = 29.0

STEEL PLATE BEAM GUARD RAIL, TYPE A

LOCATION	STATION	TO	STATION	EA.
Effingham County				
RT SHOULDER	2132+26.40		2134+13.90	187.50
RT MED SHLDR	2131+36.69		2134+24.19	287.50
LT MED SHLDR	2135+38.67		2138+13.67	275.00
RT MED SHLDR	2155+56.35		2158+31.35	275.00
LT SHOULDER	2159+42.01		2161+79.51	237.50
LT MED SHLDR	2159+45.75		2162+20.75	275.00
RT MED SHLDR	2212+81.33		2215+56.33	275.00
LT MED SHLDR	2216+71.25		2219+46.25	275.00
LT SHOULDER	2216+65.74		2218+53.24	187.50
RT SHOULDER	2246+55.92		2248+43.42	187.50
RT MED SHLDR	2255+67.11		2258+42.11	275.00
LT MED SHLDR	2259+56.64		2262+31.64	275.00
RT MED SHLDR	2297+13.04		2299+88.04	275.00
LT MED SHLDR	2301+02.39		2303+77.39	275.00
LT I-57/US 45 RAMP	30+71.08		32+21.08	150.00
RT SHOULDER	2331+05.61		2333+05.61	200.00
RT MED SHLDR	2330+17.50		2332+92.50	275.00
LT MED SHLDR	2334+06.87		2336+81.87	275.00
RT SHOULDER	2356+03.41		2358+03.41	200.00
RT MED SHLDR	2356+03.59		2357+91.09	187.50
LT SHOULDER	5381+90.76		5383+90.76	200.00
LT MED SHLDR	5407+46.70		5409+46.70	200.00
RT MED SHLDR	5404+45.59		5406+45.59	200.00
LT MED SHLDR	5407+46.10		5409+46.10	200.00
LT SHOULDER	5434+41.60		5436+41.60	200.00
RT MED SHLDR	5431+47.00		5433+47.00	200.00
LT MED SHLDR	5434+41.60		5436+41.60	200.00
Coles County				
NB Exit 57/45	02+39.80		03+77.30	137.50
SB Exit 57/45	02+52.43		04+14.93	162.50

TOTAL = 6550.00

PLOT DATE = 8/12/2007  
 FILE NAME = C:\Users\74249\Documents\74249.dgn  
 PLOT SCALE = 5/8"=1'-0"  
 USER NAME = swartzn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY