

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	44	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* D7 SAFETY 2008-2

STEEL PLATE BEAM GUARD RAIL REMOVAL

LOCATION	STATION	TO	STATION	FT.
RT MED	2133+85.41		2134+88.22	102.81
LT MED	2134+74.81		2135+77.93	103.12
LT MED	2145+95.08		2147+61.44	166.36
RT MED	2157+93.25		2158+95.49	102.24
LT MED	2158+81.33		2159+88.05	106.72
LT MED	2200+15.00		2202+41.00	226.00
RT MED	2215+17.29		2216+20.39	103.10
LT MED	2216+06.36		2217+09.57	103.21
LT SHOULDER	2215+56.00		2217+56.00	200.00
RT SHOULDER	2258+17.03		2259+19.49	102.46
RT MED	2258+04.05		2259+05.32	101.27
LT MED	2258+92.80		2259+93.93	101.13
RT SHOULDER	2332+66.19		2333+68.20	102.01
RT MED	2332+54.66		2333+55.60	100.94
LT MED	2333+43.62		2334+44.76	101.14
RT SHOULDER	2357+65.57		2358+66.52	100.95
RT MED	2357+65.81		2358+66.84	101.03

TOTAL = 2024.5

MULCH, METHOD 2

LOCATION	AREA (Acres)	TONS
Effingham Co.		
SN 025-0056	0.55	1.1
SN 025-0050	0.43	0.9
SN 025-0063	0.58	1.2
Coles Co.		
SN 015-0045	0.54	1.1

Total= 4.2

PIPE CULVERTS, SPECIAL 24"

LOCATION	STATION	TO	STATION	FEET
MEDIAN	5446+01.31	0.8' LT	5446+06.40	1.4' RT 6.0
MEDIAN	5446+06.40	1.4' RT	5446+11.43	3.7' RT 6.0

TOTAL = 12.0

*45 Degree Bend

INLET BOX, STANDARD 542531

LOCATION	STATION	NO.
MEDIAN	5444+38.49	1.0
MEDIAN	5448+31.46	1.0
MEDIAN	5497+58.09	1.0

TOTAL = 3.0

INLETS, TYPE A, SPECIAL, TYPE 8 GRATE

LOCATION	STATION	NO.
MEDIAN 1.7' RT.	5447+02.40	1.0

PIPE CULVERTS, TYPE 1 RCCP 24"

LOCATION	STATION	TO	STATION	FOOT
MEDIAN	5498+00.00			46.5
MEDIAN	5497+79.60		5497+98.83	19.2
MEDIAN	5444+59.99		5446+04.31	144.3
MEDIAN	5446+11.43		5447+02.40	91.0
MEDIAN	5447+02.40		5448+09.96	107.6
MEDIAN	5447+02.40			8.5

TOTAL = 417.1

TEMPORARY EROSION CONTROL SEEDING

LOCATION	AREA (Acres)	Lbs.
Effingham Co.		
SN 025-0056	0.55	55.0
SN 025-0050	0.43	43.0
SN 025-0063	0.58	58.0
Coles Co.		
SN 015-0045	0.54	54.0

Total= 210.0

NITROGEN FERTILIZER NUTRIENT

LOCATION	AREA (Acres)	LBS.
Effingham Co.		
SN 025-0056	0.55	49.5
SN 025-0050	0.43	38.7
SN 025-0063	0.58	52.2
Coles Co.		
SN 015-0045	0.54	48.6

Total= 189.0

PHOSPHOROUS FERTILIZER NUTRIENT

LOCATION	AREA (Acres)	LBS.
Effingham Co.		
SN 025-0056	0.55	49.5
SN 025-0050	0.43	38.7
SN 025-0063	0.58	52.2
Coles Co.		
SN 015-0045	0.54	48.6

Total= 189.0

SEEDING, CLASS 2

LOCATION	AREA (Acres)
Effingham Co.	
SN 025-0056	0.55
SN 025-0050	0.43
SN 025-0063	0.58
Coles Co.	
SN 015-0045	0.54

Total= 2.1

POTASSIUM FERTILIZER NUTRIENT

LOCATION	AREA (Acres)	LBS.
Effingham Co.		
SN 025-0056	0.55	49.5
SN 025-0050	0.43	38.7
SN 025-0063	0.58	52.2
Coles Co.		
SN 015-0045	0.54	48.6

Total= 189.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE
HORIZ.

DRAWN BY
CHECKED BY