

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1669		COLES	17	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BRIDGE REPAIR SCHEDULE

STRUCTURE NUMBER	LENGTH	CONCRETE REMOVAL	CONCRETE SUPERSTRUCTURE	REINFORCEMENT BARS, EPOXY COATED	BAR SPLICERS	PERFORMED JOINT STRIP SEAL	HOT-MIX ASPHALT SURFACE REMOVAL	KEYWAY REPAIR	PORTLAND CEMENT MORTAR FAIRING COURSE	WATERPROOFING MEMBRANE SYSTEM	HOT-MIX ASPHALT CONCRETE SURFACE COURSE, MIXTURE C, N70	BEARING PAD ADJUSTMENT
	FOOT	CU YD	CU YD	POUND	EACH	FOOT	SQ YD	FOOT	FOOT	SQ YD	TON	EACH
015-0069	71											
Stage I		1.63	1.81	123.7		16.5	122	233	233	130	18.5	12
Stage II		1.44	1.81	123.7		16.5	138	71	71	130	18.5	10
TOTAL		3.1	3.6	250	6	33	260	304	304	260	37	22
015-0070	51.33											
Stage I							91	62	62	85.5	11.5	10
Stage II							80	118	118	85.5	11.5	10
TOTAL							171	180	180	171	23	20
TOTAL		3.1	3.6	250	6	33	431	484	484	431	60	42

PAVEMENT MARKING SCHEDULE

STRUCTURE NUMBER	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	RAISED REFLECTOR PAVEMENT MARKER, REFLECTOR REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	REPLACEMENT REFLECTOR	PAINT PAVEMENT MARKING - LINE 4"
	SQ FT	SQ FT	FEET	FEET	EACH	EACH	EACH	FEET
015-0069	420	193	40	1738	4	2	4	1268
015-0070	178	205	45	1101	5	1	5	607
TOTAL	598	398	85	2839	9	3	9	1875

PLOT DATE = 8/27/2007
 PLOT SCALE = 20.0000
 PLOT USER = staff@emk

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY