

SUMMARY OF QUANTITIES

SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-15,6(RS-1)	WASHINGTON	83	3
STA. _____		TO STA. _____		
CONTRACT NO.: 76A39				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000	X231-2A SN 095-0060	X131-2A SN 095-0061	X131-2A SN 095-0062	X231-2A SN 095-0063	X231-2A SN 095-0064	Y002-1C 100% STATE
28100105	STONE RIPRAP, CLASS A3	SQ YD	12					6	6	
28101200	DUMPED RIPRAP	TON	288	288						
28200200	FILTER FABRIC	SQ YD	24					12	12	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	197.4	197.4						
40600300	AGGREGATE (PRIME COAT)	TON	718	718						
40600655	LEVELING BINDER (MACHINE METHOD), N105	TON	586	586						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2877	2877						
40600990	TEMPORARY RAMP	SQ YD	300	300						
40603095	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	30329	30329						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	135	135						
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	4799	4799						
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	229020	229020						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1423	1423						
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	834	834						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	108	108						
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	8	8						
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	20	20						
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	30	30						
44200573	CLASS A PATCHES, TYPE I, 12 INCH	SQ YD	16	16						
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	27	27						
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	64	64						
44213000	PATCHING REINFORCEMENT	SQ YD	165	165						
44213200	SAW CUTS	FOOT	825	825						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2689	2689						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	14138	14138						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	30734	30734						
50102400	CONCRETE REMOVAL	CU YD	90.8			11.2	11.2	34.2	34.2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	90.8			11.2	11.2	34.2	34.2	
50300260	BRIDGE DECK GROOVING	SQ YD	101					50.5	50.5	
50300300	PROTECTIVE COAT	SQ YD	1696			848	848			
50300530	FLOOR DRAIN EXTENSION	EACH	4		4					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10190			1860	1860	3235	3235	
50800515	BAR SPLICERS	EACH	128			30	30	34	34	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	383			82	82	109.5	109.5	

PLOT DATE = 9/15/2007
 PLOT SCALE = 1/8" = 100'-0"
 PLOT SIZE = 11" x 17"
 REFERENCE = #REF#

Rev