

SUMMARY OF QUANTITIES

FILE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	95-15,6RS-1	WASHINGTON	83	4
STA.		TO STA.		
CONTRACT NO.: 76A39				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		I000	X231-2A SN 095-0060	X131-2A SN 095-0061	X131-2A SN 095-0062	X231-2A SN 095-0063	X231-2A SN 095-0064
58700200	BRIDGE SEAT SEALER	SQ FT	486		243	243			
58700300	CONCRETE SEALER	SQ FT	19602				9801	9801	
59000200	EPOXY CRACK INJECTION	FOOT	10				10		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	182		104	78			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	412	412					
60100072	SHOULDER REMOVAL AND REPLACEMENT 5"	FOOT	171392	171392					
60107600	PIPE UNDERDRAINS 4"	FOOT	164594	164594					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	8240	8240					
60260100	INLETS TO BE ADJUSTED	EACH	2	2					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	4112.5	4112.5					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6					
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	8	8					
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4					
63200310	GUARDRAIL REMOVAL	FOOT	3762.5	3762.5					
63500105	DELINEATORS	EACH	333	333					
63500120	DELINEATOR REMOVAL	EACH	270	270					
64200105	SHOULDER RUMBLE STRIP	FOOT	173664	173664					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18					
67100100	MOBILIZATION	L SUM	1	1					
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	4		1	1	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1				
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1					
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	36330	36330					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	172500	172500					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2180	2180					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12110	12110					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1475	1475					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1475	1475					
* 72000300	SIGN PANEL - TYPE 3	SQ FT	184						184

PLOT DATE = 6/23/2007
 PLOT SCALE = 1/8" = 100'
 REFERENCE = #REF#

* SPECIALTY ITEMS