

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-(5,6)RS-1 WASHINGTON	83	10

CONTRACT NO.: 76A38

## PIPE UNDERDRAIN SCHEDULE

LOCATION	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE DRAIN REMOVAL
STA TO STA	(FT)	(FT)	(EACH)	(FT)	(FT)
<b>FAI 64 EAST BOUND</b>					
2935+25.00 TO 2943+00.00	1550	78	3	1248	1550
2943+00.00 TO 2973+00.00	6000	300	15	6240	6000
2973+00.00 TO 2981+14.00	1628	81	4	1664	1628
2983+94.00 TO 3002+00.00	3612	181	9	3744	3612
3002+00.00 TO 3033+00.00	6200	310	16	6656	6200
3033+00.00 TO 3063+00.00	6000	300	15	6240	6000
3063+00.00 TO 3093+00.00	6000	300	15	6240	6000
3093+00.00 TO 3123+00.00	6000	300	15	6240	6000
3123+00.00 TO 3153+00.00	6000	300	15	6240	6000
3153+00.00 TO 3183+00.00	6000	300	15	6240	6000
3183+00.00 TO 3213+00.00	6000	300	15	6240	6000
3213+00.00 TO 3221+25.00	1650	87	4	1664	1650
3223+55.00 TO 3243+00.00	3890	195	10	4160	3890
3243+00.00 TO 3262+84.00	3968	198	10	4160	3968
3264+46.00 TO 3273+00.00	1708	85	4	1664	1708
3273+00.00 TO 3282+12.00	1824	91	5	2080	1824
3284+18.00 TO 3288+00.00	764	38	2	832	764
3288+00.00 TO 3303+00.00	3000	150	8	3328	3000
3303+00.00 TO 3333+00.00	6000	300	15	6240	6000
3333+00.00 TO 3355+51.00	4502	225	11	4576	4502
<b>FAI 64 WEST BOUND</b>					
2935+25.00 TO 2943+00.00	1550	78	3	1248	1550
2943+00.00 TO 2973+00.00	6000	300	15	6240	6000
2973+00.00 TO 2981+14.00	1628	81	4	1664	1628
2983+94.00 TO 3002+00.00	3612	181	9	3744	3612
3002+00.00 TO 3033+00.00	6200	310	16	6656	6200
3033+00.00 TO 3063+00.00	6000	300	15	6240	6000
3063+00.00 TO 3093+00.00	6000	300	15	6240	6000
3093+00.00 TO 3123+00.00	6000	300	15	6240	6000
3123+00.00 TO 3153+00.00	6000	300	15	6240	6000
3153+00.00 TO 3183+00.00	6000	300	15	6240	6000
3183+00.00 TO 3213+00.00	6000	300	15	6240	6000
3213+00.00 TO 3221+25.00	1650	88	4	1664	1650
3223+55.00 TO 3243+00.00	3890	195	10	4160	3890
3243+00.00 TO 3262+98.00	3996	200	10	4160	3996
3264+59.00 TO 3273+00.00	1682	84	4	1664	1682
3273+00.00 TO 3282+91.00	1982	99	5	2080	1982
3284+97.00 TO 3288+00.00	606	30	2	832	606
3288+00.00 TO 3303+00.00	3000	150	8	3328	3000
3303+00.00 TO 3333+00.00	6000	300	15	6240	6000
3333+00.00 TO 3355+51.00	4502	225	11	4576	4502
<b>TOTAL=</b>	<b>164594</b>	<b>8240</b>	<b>412</b>	<b>171392</b>	<b>164594</b>

## DELINEATOR/BARRIER WALL MARKER SCHEDULE

WESTBOUND			EASTBOUND			BARRIER WALL MARKERS		
LOCATION	DELINEATOR REMOVAL	DELINEATOR	LOCATION	DELINEATOR REMOVAL	DELINEATOR	TYPE B	TYPE C	
(STATION)	(EACH)	(EACH)	(STATION)	(EACH)	(EACH)	(EACH)	(EACH)	
<b>MAINLINE</b>			<b>MAINLINE</b>					
2900+15			2900+15					
2900+62.3	1	1	2900+62.3	1	1			
2935+25			2935+25					
3355+90	77	105	3355+90	80	105			
<b>U-TURNS</b>			<b>U-TURNS</b>					
3004+50	3	4	3004+50	4	4			
3244+05	5	5	3244+05	4	4			
3350+00	5	5	3350+00	4	4			
<b>U.S. 51 INTERCHANGE</b>			<b>U.S. 51 INTERCHANGE</b>					
RAMP I (N.W.)	26	26	RAMP III (S.W.)	18	23			
RAMP II (N.E.)	16	20	RAMP IV (S.E.)	26	26			
SN 095-0061						8	8	
SN 095-0062						8	8	
SN 095-0063						8	8	
SN 095-0064						8	8	
<b>TOTALS</b>	<b>133</b>	<b>166</b>	<b>TOTALS</b>	<b>137</b>	<b>167</b>			
<b>TOTAL REMOVAL</b>							<b>270</b>	
<b>TOTAL INSTALLATION</b>							<b>333</b>	<b>32</b>

## BUTT-JOINT/TEMP. RAMPS SCHEDULE

LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMPS
STA. TO STA.	(sq yds)	(sq yds)
2934+95 to 2935+25	EB 133	20
2934+96 to 2935+25	WB 133	20
2981+15 to 2981+45	EB 133	20
2981+15 to 2981+45	WB 133	20
2983+45 to 2983+75	EB 133	20
2983+45 to 2983+75	WB 133	20
3221+15 to 3221+35	EB 133	20
3223+35 to 3223+75	EB 133	20
3281+82 to 3282+12	EB 186	20
3282+61 to 3282+91	WB 186	20
3284+18 to 3284+48	EB 186	20
3284+97 to 3285+27	WB 186	20
3355+52 to 3355+82	EB 133	20
3355+52 to 3355+82	WB 133	20
101+40 to 102+00	R1 200	5
315+00 to 315+60	R2 200	5
211+50 to 212+10	R3 200	5
401+65 to 402+25	R4 200	5
<b>TOTAL</b>	<b>2877</b>	<b>300</b>

## INLET TBA SCHEDULE

LOCATION	INLETS TO BE ADJUSTED
STATION	(EACH)
3284+25 (EB)	1
3284+95 (WB)	1
<b>TOTAL</b>	<b>2</b>

## RIPRAP SCHEDULE

LOCATION	DUMPED RIPRAP
STATION	(TON)
3099+92 (WB)	96
3139+70 (WB)	96
3182+56 (WB)	96
<b>TOTAL</b>	<b>288</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**MISC. SCHEDULES**  
 FAI ROUTE 64  
 SECTION 95-(5,6)RS-1  
 WASHINGTON COUNTY

SCALE: VERT. DATE: HORIZ. DRAWN BY: CHECKED BY: