

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95-(5,6)RS-1	WASHINGTON	83	12
TO STA.			
CONTRACT NO.: 76A39			

WESTBOUND RESURFACING SCHEDULE

LOCATION			BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	HMA SHOULDER 2 1/4"	SHOULDER RUMBLE STRIP	AGGREGATE WEDGE SHLDR TYPE B	HMA BINDER COURSE 2 1/4"	LEVELING BINDER 1"	HMA SURFACE COURSE 2"	INCIDENTAL HMA ASPHALT SURFACING	STRIP REFLECTIVE CRACK CONTROL
STA	TO	STA	(TON)	(TON)	(TON)	(FOOT)	(TON)	(TON)	(TON)	(TON)	(TON)	(FOOT)
FAI 64 WEST BOUND												
2935+25.00	TO	2943+00.00	1.77	6.58	277.53	1550.00	123.96	284.81		253.17		
2943+00.00	TO	2973+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
2973+00.00	TO	2981+45.00	1.93	7.19	302.60	1690.00	135.16	310.54		276.03		
2981+45.00	TO	2983+45.00	0.11	0.86	71.62	400.00	31.99					
2983+45.00	TO	3002+00.00	4.25	15.76	664.28	3710.00	296.71	681.71		605.97		
3002+00.00	TO	3033+00.00	7.15	26.56	1134.51	6200.00	495.86	1139.25		1012.66		
3033+00.00	TO	3063+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3063+00.00	TO	3093+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3093+00.00	TO	3123+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3123+00.00	TO	3153+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3153+00.00	TO	3183+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3183+00.00	TO	3213+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3213+00.00	TO	3221+25.00	1.90	7.02	295.43	1650.00	131.96	303.19		269.50		
3223+55.00	TO	3243+00.00	4.46	16.53	696.51	3890.00	311.11	714.79		635.37		
3243+00.00	TO	3262+98.00	4.63	17.17	738.17	3996.00	319.59	734.27		652.68		
3264+59.00	TO	3273+00.00	1.93	7.15	301.16	1682.00	134.52	309.07		274.72		644
3273+00.00	TO	3282+91.00	2.27	8.42	354.88	1982.00	158.51	364.19		323.73		345
3284+97.00	TO	3288+00.00	0.69	2.59	108.50	606.00	48.47	111.35		98.98		
3288+00.00	TO	3303+00.00	3.43	12.75	537.15	3000.00	239.93	551.25		490.00		362
3303+00.00	TO	3333+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3333+00.00	TO	3355+81.00	5.23	19.39	816.83	4562.00	364.85	838.27		745.12		
RAMPS												
101+40.00	TO	109+15.00	1.13	2.58	183.19	1724.00	100.46		81.03	162.06		
109+15.00	TO	120+79.00	0.96	0.58	40.38	166.00	150.88		84.38	168.76		
200+00.00	TO	206+95.00	0.75	1.08	76.51	1390.00	90.09		59.45	118.89		
206+95.00	TO	212+10.00	0.76	1.72	121.77	310.00	66.76		53.87	107.72		
SUB TOTAL =			98.5	358	15315	86508	7040	15163	279	14035		1351
GRAND TOTAL =			197.4	718	30734	173664	14138	30329	586	28130	135	2689

PLOT DATE = 9/6/2007
 FILE NAME = \\s01\p1\proj\95-5,6\rs-1\95-5,6\rs-1\95-5,6\rs-1.dgn
 PLOT SCALE = 50,000 / IN
 USER NAME = dmshamlin

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

RESURFACING SCHEDULES

FAI ROUTE 64
SECTION 95-(5,6)RS-1
WASHINGTON COUNTY

SCALE: VERT. _____
 HORIZ. _____

DRAWN BY _____
 CHECKED BY _____