FAS ROUTE NO	SEC	COUNTY	TOTAL SHEETS	SHEET NO
–	*	DEKALB	21	2

ILLINOIS PROJECT BRS-1122(107)

* 04-00206-00-BR

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	FEDERAL FUNDING CODE X-020-2A (STRUCTURE)	FEDERAL FUNDING CODE X-1000 (ROADWAY)	
	20200100	EARTH EXCAVATION	CU YD	1170	0	1,170	
	20400800	FURNISHED EXCAVATION	CU YD	3270	0	3,270	
	20800150	TRENCH BACKFILL	CU YD	25	0	25	
*	25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.49	0.22	1.27	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800	0	800	
	28000300	TEMPORARY DITCH CHECKS	EACH	25	0	25	
	28000400	PERIMETER EROSION BARRIER	FOOT	400	0	400	
	31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1561	0	1,561	
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	76	0	76	
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.9	0	7.9	
	40600982	HOT-MIX ASPHALT SURFACE COURSE REMOVAL - BUTT JOINT	SQ YD	532	0	532	
	40603080	HOT MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2253	0	2,253	
	40603305	HOT MIX ASPHALT SURFACE SOURSE, MIX "C", N30	TON	1065	0	1,065	
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2637	0	2,637	
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	689	0	689	
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	0	
	50300225	CONCRETE STRUCTURES	CU YD	25.4	25.4	0	
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	152.6	152.6	0	
	50300260	BRIDGE DECK GROOVING	SQ YD	222	222	0	
	50300300	PROTECTIVE COAT	SQ YD	242	242	0	
	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6595	6595	0	
	50700305	HARDWARE	POUND	3084	3084	0	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	23,460	23,460	0	
	50901050	STEEL RAILING , TYPE SM	FOOT	87	87	0	
	51201005	FURNISHING METAL SHELL PILES 12"	FOOT	583	583	0	
	51203200	TEST PILE METAL SHELLS	EACH	1	1	0	
	51202305	DRIVING PILES	FOOT	583	583	0	
	51500100	NAME PLATES	EACH	1	1	0	
	542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	84	0	84	
	542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	250	0	250	
	54200451	PIPE CULVERTS, TYPE 1 RCCP 36"	FOOT	115	0	115	
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	940	0	940	
△	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	550	0	550	
△	63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4	0	4	
△*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	0	3	
△*	63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	0	1	
*	63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	414	0	414	
*	67100100	MOBILIZATION	L SUM	1	0	1	
△	78001100	PAINT PAVEMENT MARKINGS - LETTERS AND SYMBOLS	SQ FT	54.2	0	54	
△	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4268	0	4,268	
△	78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	754	0	754	
△	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	43	0	43	
△	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	78	0	78	
△*	78200455	BIDIRECTIONAL GUARD RAIL REFLECTORS	EACH	12	0	12	
△*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	0	4	
*	X5121800	PERMANENT STEEL SHEET PILING	SQ FT	3550	3550	0	

QUANTITY NOTES:
△ SPECIALTY ITEMS – * SEE SPECIAL PROVISIONS
PERIMETER EROSION BARRIER IS AN ESTIMATED QUANTITY. LOCATIONS ARE TO BE DESIGNATED IN THE FIELD BY THE ENGINEER.

REVISED 09/21/2007

SUMMARY OF QUANTITIES
SECTION 04-00206-00-BR
CHERRY VALLEY ROAD
DEKALB COUNTY