

CONTRACT NO. 88798

F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	*	**	97	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	US 67/IL 135	
* (101BY8R & (28BR))				
** WARREN COUNTIES				

GUARDRAIL SCHEDULE						
LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT) (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (FLARED) (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	GUARDRAIL REMOVAL (FOOT)	TERMINAL MARKER DIRECT APPLIED (EACH)
RT 70+72.00 TO 72+87.00					215	
LT 70+72.00 TO 72+87.00					215	
RT 73+30 TO 74+97					167	
LT 73+30 TO 75+72					242	
RT 69+89.85						1
RT 69+89.85 TO 70+39.85			1			
RT 70+39.85 TO 72+14.85	175					
RT 72+14.85 TO 72+58.00				1		
LT 70+89.85						1
LT 70+89.85 TO 71+39.85		1				
LT 71+39.85 TO 72+14.85	75					
LT 72+14.85 TO 72+58.00				1		
RT 73+46.00 TO 73+89.15				1		
LT 73+46.00 TO 73+89.15				1		
RT 73+89.15 TO 74+89.15	100					
RT 74+89.15 TO 75+39.15		1				
RT 75+39.15						1
LT 73+89.15 TO 75+64.15	175					
LT 75+64.15 TO 76+14.15		1				
LT 76+14.15						1
RT 828+25.00 TO 828+62.00					37	
LT 827+63.00 TO 828+62.00					99	
RT 829+86.00 TO 831+10.00					124	
LT 829+86.00 TO 832+13.00					227	
RT 825+92.97						1
RT 825+92.97 TO 826+42.97		1				
RT 826+42.97 TO 828+17.97	175					
RT 828+17.97 TO 828+61.12				1		
LT 826+92.97						1
LT 826+92.97 TO 827+42.97		1				
LT 827+42.97 TO 828+17.97	75					
LT 828+17.97 TO 828+61.12				1		
RT 829+86.87 TO 830+30.02				1		
RT 830+30.02 TO 831+05.02	75					
RT 831+05.02 TO 831+55.02		1				
RT 831+55.02						1
LT 829+86.87 TO 830+30.02				1		
LT 830+30.02 TO 832+05.02	175					
LT 832+05.02 TO 832+55.02		1				
LT 832+55.02						1
TOTAL	1025	7	1	8	1326	8

MISCELLANEOUS SCHEDULE								
STA LOCATION	ENGINEER'S FIELD OFFICE TYPE A (CAL MO)	MOBILIZATION (L SUM)	TRAFFIC CONTROL AND PROTECTION				TRAFFIC CONTROL SURVEILLANCE (CAL DA)	CONSTRUCTION LAYOUT (L SUM)
			STANDARD 701201 (L SUM)	STANDARD 701321 (EACH)	STANDARD 701306 (L SUM)	STANDARD 701326 (L SUM)		
TOM'S CREEK CK	6	0.5	0.5	1	0.5	0.5	15	0.5
MIDDLE HENDERSON CK	6	0.5	0.5	1	0.5	0.5	15	0.5
TOTAL	12	1	1	2	1	1	30	1

DRAINAGE SCHEDULE							
STA LOCATION	PIPE CULVERTS, CLASS D, TYPE 1, 24" (FOOT)	METAL END SECTIONS 12" (EACH)	METAL END SECTIONS 24" (EACH)	PIPE DRAINS 12" (FOOT)	CLASS SI CONCRETE (OUTLET) (CU. YD.)	TYPE B INLET BOX STANDARD 609006 (EACH)	CONCRETE THRUST BLOCKS (EACH)
69+00 RT					8.8		
69+00 LT					7.7		
69+75 TO 70+41 LT	66		2				
73+71.00 RT		1		33		1	1
73+71.00 LT		1		46		1	1
828+47.50 RT		1		25		1	1
828+47.50 LT		1		47		1	1
TOTAL	66	4	2	151	16.5	4	4

REMOVAL SCHEDULE						
LOCATION	GUTTER REMOVAL (FT)	GUTTER OUTLET REMOVAL (EACH)	PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	PIPE CULVERT REMOVAL (FOOT)	EROSION CONTROL CURB REMOVAL (FOOT)
69+00.00 TO 69+54.00 RT	54					
69+00.00 TO 69+54.00 LT	54					
69+54.00 RT/LT		2				
70+03 LT					22	
72+22.00 TO 72+87.00			231			
73+30 TO 74+97 RT						167
73+30 TO 75+70 LT						240
73+30.00 TO 73+82.00			185			
828+25.95 TO 828+62.00			128	72		
828+27 LT					48	1
828+27 RT					19	1
829+85 RT					30	
829+86.00 TO 830+22.04			112	22		
TOTAL	108	2	656	94	119	407

PATCHING QUANTITIES				
LOCATION	CLASS D PATCHES, TYPE I, 15 INCH (SQ. YD.)	CLASS D PATCHES, TYPE II, 15 INCH (SQ. YD.)	CLASS D PATCHES TYPE III, 15 INCH (SQ. YD.)	CLASS D PATCHES, TYPE IV, 15 INCH (SQ. YD.)
824+00 TO 828+25.95		58.7	98.7	31.1
830+22.04 TO 833+50		32	15.6	35.6
69+00 TO 72+22	2.7	16		
73+82 TO 77+00		33.8		
SUBTOTAL	2.7	140.5	114.3	66.7
+15% WINTER BREAKUP	0.4	21.1	17.1	10
TOTAL	3	162	131	77

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: NO SCALE DRAWN BY: B.A.D.
DATE: 04-02-04 CHECKED BY: M.A.R.