

**CONTRACT NO. 88798**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			97	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (101BY1BR & (28BR1) ** WARREN COUNTIES				

**STAGING SCHEDULE**

LOCATION	TEMPORARY RAMP (SQ YD)	TEMPORARY BRIDGE TRAFFIC SIGNALS (EACH)	TEMPORARY RUMBLE STRIP (EACH)	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
69+00.00	18						
72+28.00	24						
73+76.00	24						
77+00.00	24						
71+20.00						1	1
71+22.00 TO 74+82.00				360			
71+32.00 TO 74+72.00					340		
74+75.00							1
74+90.00						1	
824+00.00	16						
825+50.00	23						
828+25.95	27						
828+32.00	24						
828+62.00 LT	3						
829+86.00 LT	3						
830+16.00	24						
833+50.00	16						
827+30.00						1	1
827+34.00 TO 831+14.00				380	380		
831+20.00						1	1
TOM'S CK		1	3				
MIDDLE HENDERSON CK		1					
TOTAL	226	2	3	740	720	4	4

**TREE SCHEDULE**

LOCATION	TREE, BETULA NIGRA (RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED (EACH)
830+20 TO 833+50 RT	3	3	4	3
TOTAL	3	3	4	3

**GUARDRAIL & BARRIER WALL MARKERS**

LOCATION	GUARDRAIL MARKERS, TYPE A (EACH)	BARRIER WALL MARKERS, TYPE C (EACH)
71+39.5 TO 72+58 LT	3	
70+39.5 TO 72+58 RT	4	
72+58 TO 73+46 LT & RT		6
73+46 TO 74+89.5 RT	3	
73+46 TO 75+64.5 LT	4	
826+42.62 TO 828+61.12 RT	4	
827+42.62 TO 828+61.12 LT	3	
828+61.95 TO 829+86.04 LT & RT		6
829+86.87 TO 831+05.37 RT	3	
829+86.87 TO 832+05.37 LT	4	
TOTAL	28	12

**PAVEMENT MARKING SCHEDULE**

LOCATION	SHORT-TERM PAVEMENT MARKING (FOOT)	TEMPORARY PAVEMENT MARKING-LINE 4" (FOOT)	PAVEMENT MARKING TAPE, TY III 4" (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ. FT.)	PAINT PAVEMENT MARKING LINE	
						4" WHITE (FT)	4" YELLOW (FT)
69+00.00 TO 77+00.00	352			117	533	1600	1600
69+10.00 TO 77+10.00 STAGE 1		1600		533			
69+10.00 TO 72+22.00 STAGE 2		624		208			
72+22.00 TO 73+82.00 STAGE 2			320	107			
73+82.00 TO 77+10.00 STAGE 2		656		219			
824+00.00 TO 833+50.00	524			175	633	1900	1188
825+24.00 TO 833+25.00 STAGE 1		1602		534			
825+24.00 TO 828+26.00 STAGE 2		604		201			
828+26.00 TO 830+22.00 STAGE 2			392	131			
830+22.00 TO 833+25.00 STAGE 2		606		202			
TOTAL	876	5692	712	2427	1166	6288	

**PERMANENT SURVEY MARKER SCHEDULE**

LOCATION	POINT TYPE	EACH
69+00.00	P.O.T.	1
77+00.00	P.O.T.	1
SN 094-0049	BRIDGE	1
824+00.00	P.O.T.	1
831+50.00	P.O.T.	1
SN 094-0002	BRIDGE	1
TOTAL		6

**GUARDRAIL AGGREGATE EROSION CONTROL**

LOCATION	TONS
69+42 TO 72+58 RT	148
70+61 TO 72+58 LT	43
73+46 TO 75+75 RT	60
73+46 TO 76+46 LT	76
825+65 TO 828+62 RT	62
826+74 TO 828+62 LT	39
829+86 TO 831+84 RT	41
829+86 TO 832+82 LT	62
TOTAL	531

**FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS**

STATION	OFFSET	EACH
827+50.00	70' RT	1
828+50.00	150' RT	1
830+00.00	150' RT	1
830+25.00	70' RT	1
TOTAL		4

**TRAINEES**

LOCATION	HOURS
ENTIRE PROJECT	500
TOTAL	500

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES OF QUANTITIES**

SCALE: NO SCALE  
DATE: 04-02-04

DRAWN BY: B.A.D.  
CHECKED BY: M.A.R.