

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(108)BR, BR-1	MCDONOUGH	80	10
STA. 63+00		TO STA. 74+00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**50200100 STRUCTURE EXCAVATION**

LOCATION	QUANTITY (CU YD)
Sta. 65+75 to 68+00	914
TOTAL =	914

**54001000 BOX CULVERT END SECTIONS**

LOCATION	QUANTITY (EACH)
RT. STA. 73+10	1
LT. STA. 73+10	1
TOTAL =	2

**54020805 PRECAST CONCRETE BOX CULVERT 8'X5' (M273)**

LOCATION	QUANTITY (FOOT)
RT. STA. 73+10	4
LT. STA. 73+10	4
TOTAL =	8

**54215550 METAL END SECTIONS 15"**

LOCATION	QUANTITY (EACH)
RT. STA. 64+50	1
RT. STA. 65+16	1
TOTAL =	2

**54248510 CONCRETE COLLAR**

LOCATION	QUANTITY (CU YD)
STA. 73+10	2.4
TOTAL =	2.4

**54200220 PIPE CULVERTS, CLASS D, TYPE 1 15"**

LOCATION	QUANTITY (FOOT)
RT. STA. 64+50 TO 65+16	66
TOTAL =	66

**63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A**

LOCATION	QUANTITY (FOOT)
RT. STA. 65+53 TO 67+28	175
RT. STA. 67+78 TO 70+03	225
LT. STA. 64+15 TO 66+40	225
LT. STA. 67+15 TO 69+40	225
TOTAL =	850

**63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES**

LOCATION	QUANTITY (FOOT)
LT. STA. 65+65 to 67+15	50
RT. STA. 67+28 to 67+78	50
TOTAL =	100

**63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)**

LOCATION	QUANTITY (EACH)
STATION	
NE	1
SE	1
SW	1
TOTAL =	3

**63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)**

LOCATION	QUANTITY (EACH)
STATION	
NW	1
TOTAL =	1

**63200305 STEEL PLATE BEAM GUARDRAIL REMOVAL**

LOCATION	QUANTITY (FOOT)
LT. STA. 66+20 TO 67+29	109
RT. STA. 66+48 TO 67+48	100
LT. STA. 67+58 TO 68+58	100
RT. STA. 67+78 TO 67+87	109
TOTAL =	418

**66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS**

LOCATION	QUANTITY (EACH)
RT. STA. 64+50 - 40' RT.	1
RT. STA. 65+56 - 52' RT.	1
RT. STA. 67+00 - 55' RT.	1
RT. STA. 67+50 - 75' RT.	1
RT. STA. 68+00 - 75' RT.	1
RT. STA. 68+50 - 50' RT.	1
LT. STA. 65+00 - 40' LT.	1
LT. STA. 66+50 - 80' LT.	1
LT. STA. 67+00 - 80' LT.	1
LT. STA. 68+00 - 40' LT.	1
TOTAL =	10

**66700205 PERMANENT SURVEY MARKERS, TYPE 1**

LOCATION	QUANTITY (EACH)
ON STRUCTURE	1
TOTAL =	1

**67000400 ENGINEER'S FIELD OFFICE, TYPE A**

LOCATION	QUANTITY (CAL MO)
JOBSITE	4
TOTAL =	4

**67100100 MOBILIZATION**

LOCATION	QUANTITY (L SUM)
JOBSITE	1
TOTAL =	1

**70100405 TRAFFIC CONTROL AND PROTECTION, STD 701321**

LOCATION	QUANTITY (EACH)
STATION	1
Jobsite	
TOTAL =	1

**70100500 TRAFFIC CONTROL AND PROTECTION, STD 701326**

LOCATION	QUANTITY (L SUM)
STATION	1
Jobsite	
TOTAL =	1

**70103815 TRAFFIC CONTROL SURVEILLANCE**

LOCATION	QUANTITY (CAL DA)
STATION	5
Jobsite	
TOTAL =	5

**70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS**

LOCATION	QUANTITY (EACH)
STATION	1
Jobsite	
TOTAL =	1

**70106700 TEMPORARY RUMBLE STRIP**

LOCATION	QUANTITY (EACH)
STATION	
North Project Limit	3
South Project Limit	3
TOTAL =	6

**70300220 TEMPORARY PAVEMENT MARKING - LINE 4"**

LOCATION	QUANTITY (FOOT)
Sta. 63+00 to 74+00	2200
	275
GRAND TOTAL =	2475

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.  
DATE

DRAWN BY  
CHECKED BY