

CONTRACT NO. 94967				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(51-23)B-3	LAWRENCE	56	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			801.FED. 201.STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	X071-2A	
20100500	TREE REMOVAL, ACRES	ACRE	0.6	0.6		
20200100	EARTH EXCAVATION	CU YD	4769	4769		
20300100	CHANNEL EXCAVATION	CU YD	12964	12964		
20600110	GRANULAR EMBANKMENT, SPECIAL	TON	3230	3230		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	191		191	
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1602	1602		
* 25000200	SEEDING, CLASS 2	ACRE	2.8	2.8		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	252	252		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	252	252		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	252	252		
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	5.6	5.6		
* 25100115	MULCH, METHOD 2	ACRE	2.8	2.8		
* 25100630	EROSION CONTROL BLANKET	SQ YD	670	670		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	900		
28000300	TEMPORARY DITCH CHECKS	EACH	20	20		
28000400	PERIMETER EROSION BARRIER	FOOT	1200	1200		
28100105	STONE RIPRAP, CLASS A3	SQ YD	180	180		
28100109	STONE RIPRAP, CLASS A5	SQ YD	3098		3098	
28200200	FILTER FABRIC	SQ YD	3298	200	3098	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	670	670		
35650700	BASE COURSE WIDENING	SQ YD	590	590		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1680	1680		
40600300	AGGREGATE (PRIME COAT)	TON	3	3		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	440	440		
40600990	TEMPORARY RAMP	SQ YD	84	84		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	140	140		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	110	110		
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	2090	2090		
44000100	PAVEMENT REMOVAL	SQ YD	770	770		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	950	950		
44000700	APPROACH SLAB REMOVAL	SQ YD	230	230		
44004000	PAVED DITCH REMOVAL	FOOT	510	510		
44004250	PAVED SHOULDER REMOVAL	SQ YD	520	520		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	90	90		

SUMMARY OF QUANTITIES			801.FED. 201.STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	X071-2A	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	520	520		
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	230	230		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	330	330		
48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SQ YD	850	850		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	42	42		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	41	41		
50200100	STRUCTURE EXCAVATION	CU YD	192		192	
50200300	COFFERDAM EXCAVATION	CU YD	270		270	
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	149		149	
50200500	COFFERDAMS	EACH	2		2	
50300100	FLOOR DRAINS	EACH	24		24	
50300225	CONCRETE STRUCTURES	CU YD	583.9		583.9	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	624.7		624.7	
50300260	BRIDGE DECK GROOVING	SQ YD	1907		1907	
50300265	SEAL COAT CONCRETE	CU YD	19.2		19.2	
50300280	CONCRETE ENCASMENT	CU YD	8.8		8.8	
50300300	PROTECTIVE COAT	SQ YD	2430		2430	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	4464		4464	
50800105	REINFORCEMENT BARS	POUND	312	312		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	254,330		254,330	
50800515	BAR SPLICERS	EACH	1920		1920	
51201610	FURNISHING STEEL PILES HP12X63	FOOT	660		660	
51202305	DRIVING PILES	FOOT	660		660	
51203610	TEST PILE STEEL HP12X63	EACH	2		2	
51204650	PILE SHOES	EACH	13		13	
51500100	NAME PLATES	EACH	1		1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	86		86	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	72		72	
58700300	CONCRETE SEALER	SQ FT	1227		1227	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. / HORIZ.
DATE

DRAWN BY
CHECKED BY