F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8899	03-00026-00-RP	MADISON	107	4
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97295

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

J000

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	11
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	5402
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	627
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	268
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2398
72000100	SIGN PANEL - TYPE 1	SQ FT	74
72900100	METAL POST - TYPE A	FOOT	102
72900200	METAL POST - TYPE B	FOOT	62
* 78008200	POLYUREA PAVEMENT MARKING TYPE 1-LETTERS AND SYMBOLS	SQ FT	11
* 78008210	POLYUREA PAVEMENT MARKING TYPE 1-LINE 4"	FOOT	5402
* 78008230	POLYUREA PAVEMENT MARKING TYPE 1-LINE 6"	FOOT	627
* 78008250	POLYUREA PAVEMENT MARKING TYPE 1-LINE 12"	FOOT	268
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	150
Z0022800	FENCE REMOVAL	FOOT	13
XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	345
XX001607	RETAINING WALL, SPECIAL	SQ FT	697
XX001796	INLETS, SPECIAL, TYPE 5	EACH	1
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	129
XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
XZ127900	RETAINING WALL REMOVAL	FOOT	285

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY

* SPECIALTY ITEMS

FINAL SURVEY — NOTE BOOK NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED — BY — DATE

ORIGINAL SURVEY — NOTE BOOK NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED — BY — DATE

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325, Granite City, Illinois 62040, Phone:(618)877-1400/(618)452-5535, Fax:(618)452-5541
100 North Research Drive, Edwardsville, Illinois 62025, Phone: (618)659-0900/(618) 659-0900, Fax: (618)659-0941

SUMMARY OF QUANTITIES
F.A.U. ROUTE 8899
GLEN CROSSING ROAD
GLEN CARBON, ILLINOIS
SECTION No. 03-00026-00-RP

REVISIONS			
NO.	DATE	BY	REMARKS

DWG. NO.

SCALE: N.T.S.

DSN. BY:	BFK	DATE:	12/13/06	SHEET
DWN. BY:	JJB	DATE:	12/13/06	4
CHK'D:	BFK	DATE:	12/13/06	
JOB NO.	040630	DGN. NAME:	GENNOTES	OF 107 SHTS