

### STORM SEWER SCHEDULE (CONT.)

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8899 03-00026-00-RP	MADISON		107	25
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**CONTRACT NO. 97295**

STRUCTURE ID	LOCATION	RCCP TYPE 1 CLASS IV (FOOT)		RCCP TYPE 1 CLASS III (FOOT)		PVC, SS CLASS B, TYPE 1 (FOOT)	PIPE CULVERTS, TYPE 1, CMP (FOOT)	STORM SEWER, TYPE 1, RCEP (FOOT)			RCCP TYPE 2 CLASS III (FOOT)					TRENCH BACKFILL (CU YD)	
		15"	18"	30"	36"			15"	15"	Span 23", Rise 14"	Span 38", Rise 24"	Span 45", Rise 29"	15"	18"	24"		30"
GLEN CROSSING ROAD																	
H-12 TO H-09	STA. 29+19.75 - 18.50' LT TO STA. 28+76.75 - 18.50' LT																21
H-09 TO H-07	STA. 28+76.75 - 18.50' LT TO STA. 28+33.89 - 18.50' LT																15
H-07 TO H-05	STA. 28+33.89 - 18.50' LT TO STA. 27+96.56 - 18.50' LT																16
H-05 TO J-01	STA. 27+96.56 - 18.50' LT TO STA. 27+63.00 - 21.18' LT																22
J-01 TO J-01A	STA. 27+63.00 - 21.18' LT TO STA. 27+63.00 - 39.18' LT																0
JAMIE LYNN LANE																	
G-12 TO G-13	STA. 100+62.41 - 16.00' LT TO STA. 100+62.41 - 16.00' RT																7
G-13 TO G-01B	STA. 100+62.41 - 16.00' RT TO STA. 21+79.87 - 6.50' LT																48
WATERFORD LANE																	
H-16B TO H-16A	STA. 100+81.38 - 46.10' LT TO STA. 100+81.51 - 17.70' LT				21												0
H-16A TO H-16	STA. 100+81.51 - 17.70' LT TO STA. 100+81.62 - 18.44' RT				32												4
H-16 TO H-17	STA. 100+81.62 - 18.44' RT TO STA. 31+58.39 - 28.25' RT														49		6
H-19A TO H-19	STA. 100+71.04 - 48.63' LT TO STA. 32+07.53 - 25.49' RT				42												0
OAKLAWN ROAD																	
O-01 TO O-02	STA. 101+05.27 - 14.48' RT TO STA. 101+05.22 - 15.16' LT	27															3
O-02 TO O-03	STA. 101+05.22 - 15.16' LT TO STA. 101+05.23 - 19.92' LT						2										0
SUBTOTAL (PREVIOUS SHEET)		502	132	164	115	36	0	14	85	218	816	627	40	0	157	2084	
SUBTOTAL (THIS SHEET)		27	0	95	0	0	2	0	0	139	95	0	0	49	0	142	
TOTAL		529	132	259	115	36	2	14	85	357	911	627	40	49	157	2226	

### FENCE TO BE REMOVED AND RE-ERECTED SCHEDULE

EXISTING LOCATION	LENGTH (FOOT)	PROPOSED LOCATION
GLEN CROSSING ROAD		
STA. 25+01.09 - 13.02' LT TO STA. 25+17.07 - 13.33' LT	16	STA. 25+01.09 - 26.50' LT TO STA. 25+17.07 - 26.83' LT
STA. 25+17.07 - 13.33' LT TO STA. 25+17.20 - 29.35' LT	16	STA. 25+17.07 - 26.83' LT TO STA. 25+17.20 - 42.85' LT
STA. 25+37.22 - 13.24' LT TO STA. 25+37.12 - 29.49' LT	16	STA. 25+37.22 - 26.74' LT TO STA. 25+37.12 - 43.00' LT
STA. 25+37.22 - 13.24' LT TO STA. 28+34.16 - 15.00' LT	297	STA. 25+37.22 - 26.74' LT TO STA. 28+34.16 - 28.50' LT
<b>TOTAL</b>	<b>345</b>	

### FENCE REMOVAL SCHEDULE

EXISTING LOCATION	LENGTH (FOOT)
GLEN CROSSING ROAD	
STA. 28+34.16 - 15.00' LT TO STA. 28+33.88 - 28.19' LT	13
<b>TOTAL</b>	<b>13</b>

### MEDIAN REMOVAL SCHEDULE

LOCATION	AREA (SQ FT)
SQUIRE DRIVE	
STA. 100+45.00 TO STA. 100+85.86	232
<b>TOTAL</b>	<b>232</b>

### SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1 (AC)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (TON)
GLEN CROSSING ROAD					
STA. 10+51.02 TO STA. 38+81.24	1.02	91.80	91.80	91.80	2.04
BOLLINGER STREET					
STA. 100+26.22 TO STA. 101+58.19	0.03	2.70	2.70	2.70	0.06
CEDAR AVENUE					
STA. 100+21.82 TO STA. 100+77.05	0.03	2.70	2.70	2.70	0.06
JAMIE LYNN					
STA. 100+21.78 TO STA. 100+88.17	0.03	2.70	2.70	2.70	0.06
OAKLAWN ROAD					
STA. 100+13.00 TO STA. 101+38.30	0.05	4.50	4.50	4.50	0.10
SQUIRE DRIVE					
STA. 100+13.00 TO STA. 101+10.48	0.04	3.60	3.60	3.60	0.08
WATERFORD LANE					
STA. 100+13.00 TO STA. 100+86.49	0.07	6.30	6.30	6.30	0.14
<b>TOTAL</b>	<b>1</b>	<b>114</b>	<b>114</b>	<b>114</b>	<b>3</b>

### TRENCH BACKFILL SCHEDULE

LOCATION	TRENCH BACKFILL (CU YD)
STORM SEWER SCHEDULE	
	2226
STORM SEWER REMOVAL SCHEDULE	
	241
CULVERT REMOVAL SCHEDULE	
	61
<b>TOTAL</b>	<b>2528</b>

**Juneau Associates, Inc. P.C.**  
 CONSULTING ENGINEERS AND LAND SURVEYORS  
 2100 State Street, P.O. Box 1325  
 Granite City, Illinois 62040  
 Phone: (618) 877-1400/(618) 482-5500  
 Fax: (618) 482-5541

**QUANTITY SCHEDULES**  
 F.A.U. ROUTE 8899  
 GLEN CROSSING ROAD  
 GLEN CARBON, ILLINOIS  
 SECTION No. 03-00026-00-RP

REVISIONS				SCALE:	
NO.	DATE	BY	REMARKS	N.T.S.	
				DSN. BY: BFK	DATE: 12/13/06
				DWN. BY: JJB	DATE: 12/13/06
				CHKD: BFK	DATE: 12/13/06
DWG. NO.				JOB NO. 040630	DGN. NAME: comsch

DATE	BY

DATE	BY