F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00054-00-WR	MADISON	110	34
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97320

FINAL SURVEY NOTE BOOK ____ NO. ____ | DATE | BY | SURVEYED | PLOTTED | TEMPLATE | AREAS | AREAS CHECKED

GENEVIEVE PRATT PROPERITES
PARCEL 6

NOBEL BROADCASTING
OF ST. LOUIS, INC.
PARCEL 5

WASTE MANAGEMENT OF ILLINOIS, INC.
MILAM LANDFILL
PARCEL 3

MATCH LINE STA. 121+20.00

MATCH LINE STA. 126+80.00

EXISTING R.O.W.

CONSTRUCTION LIMITS

P.C.C. CURB & GUTTER TYPE B-6.24

HOT-MIX ASPHALT SHOULDER

50'

18'

16'

12'

FENCE

GRASS

TILE

"GONG" P.S. 10.27' S 61°15' E

122 | 123 | 124 | 125+00 | 126

87°11'47"

85°05'45"

℄ CONSTRUCTION

OLD MADISON ROAD

50.00'R

24" CMP

50.5'

ASPHALT 24'

TEMP. EASE.

122+84.74 50.00' RT

122+18.74 50.00' RT

122+84.74 74.00' RT

122+18.74 74.00' RT

0 20 40
SCALE

IN W. SIDE 2ND POWER POLE, N. OF WASTE MANAGEMENT MIDDLE ENTRANCE ON E. SIDE OF OLD MADISON ROAD
ELEV. 405.46

ORIGINAL SURVEY | DATE | BY | SURVEYED | PLOTTED | TEMPLATE | AREAS | AREAS CHECKED | NOTE BOOK ____ NO. ____

420 / 415 / 410 / 405 / 400 / 395 / 390

K = 133
100.00' V.C.

PROPOSED ROADWAY PROFILE

VPI STA. 124+00.00
ELEVATION 408.65

K = 167
100.00' V.C.

VPI STA. 126+00.00
ELEVATION 408.65

408.47

+0.41% -0.30%

-0.34% +0.41%

VPI STA. 122+60.00
ELEVATION 408.03

EXISTING ROADWAY PROFILE

SSD = 982'
K = 140
100.00' V.C.

-0.30% +0.30%

VPI STA. 125+00.00
ELEVATION 408.35

+0.30% -0.32%

SSD = 1122'
K = 161
100.00' V.C.

408.43

408.35 408.47 | 408.39 408.53 | 408.44 408.56 | 408.45 408.57 | 408.44 408.56 | 408.43 408.52 | 408.36 408.46 | 408.28 408.43

125+50 | 126+00 | 126+50

408.35 408.47 | 408.34 408.40 | 408.27 408.33 | 408.16 408.27 | 408.11 408.20 | 408.04 408.15 | 407.97 408.12 | 407.93 408.13 | 407.91 408.17 | 408.11 408.24 | 408.16 408.32 | 408.17 408.40 | 408.20 408.48 | 408.22 408.54 | 408.24 408.56 | 408.22 408.56 | 408.20 408.53 | 408.21 408.47 | 408.24 408.44 | 408.26 408.43 | 408.31 408.44

121+50 | 122+00 | 122+50 | 123+00 | 123+50 | 124+00 | 124+50 | 125+00

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325, Granite City, Illinois 62040, Phone (618) 876-7440/(618) 452-5539, Fax (618) 452-0541
100 North Kaskaskia Drive, Edwardsville, Illinois 62025, Phone (618) 656-0900/(618) 656-0800, Fax (618) 659-0541

PLAN AND PROFILE

OLD MADISON ROAD
MADISON, ILLINOIS
SECTION No. 05-00054-00-WR

REVISIONS			
NO.	DATE	BY	REMARKS

DWG. NO:

SCALE: 1 Inch = 20 feet

DSN. BY:	BFK	DATE:	06/06/07
DWN. BY:	JDH	DATE:	06/06/07
CHK'D:	BFK	DATE:	06/06/07
JOB NO:	E061003	DGN. NAME:	PLAN.DS

SHEET 34 OF 110 SHTS