

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	57B-3I	COOK	62	5
STA. 20+23.42		TO STA. 28+00.00		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 60440

100% STATE

100% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY.	RDWY 1000-2A	BRIDGE X071-2A	LIGHTING Y030-1E
55039700	STORM SEWERS TO BE CLEANED	FT	330	330		
55100300	STORM SEWER REMOVAL 8"	FT	147	147		
55100700	STORM SEWER REMOVAL 15"	FT	93	93		
* 56103520	DUCTILE IRON PIPE WATERMAIN - 24 INCHES	FT	48	48		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	168		168	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FT	235		235	
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	4	4		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FT	723	723		
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FT	797	797		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2671	2671		
60622000	CONCRETE MEDIAN, TYPE SM-2.12	SQ FT	1059	1059		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FT	400	400		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	164	164		
70300100	SHORT-TERM PAVEMENT MARKING	FT	543	543		
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FT	3106	3106		
70300520	PAVEMENT MARKING TAPE TYPE III, 4"	FT	10563	10563		
70300570	PAVEMENT MARKING TAPE TYPE III, 24"	FT	24	24		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1035	1035		
70400100	TEMPORARY CONCRETE BARRIER	FT	429	429		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FT	429	429		
* 78008300	POLYUREA PAVEMENT MARKING, TYPE II - LETTERS AND SYMBOLS	SQ FT	78	78		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY.	RDWY 1000-2A	BRIDGE X071-2A	LIGHTING Y030-1E
* 78008310	POLYUREA PAVEMENT MARKING, TYPE II - LINE 4"	FT	7815	7815		
* 78008330	POLYUREA PAVEMENT MARKING, TYPE II - LINE 6"	FT	202	202		
* 78008350	POLYUREA PAVEMENT MARKING, TYPE II - LINE 12"	FT	588	588		
* 78008370	POLYUREA PAVEMENT MARKING, TYPE II - LINE 24"	FT	84	84		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	118	118		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8		
78300405	PAVEMENT MARKING REMOVAL	FT	4102	4102		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FT	700			700
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FT	700			700
* X8300100	LIGHT POLE, ALUMINUM, WITH MAST ARM, INSTALL ONLY	EACH	7			7
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FT	63			63
* 84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	7			7
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	7			7
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FT	700			700
* B2000764	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	20	20		
X0321600	FORM LINER TEXTURED SURFACE	SQ FT	2100		2100	
* X0322738	ELECTRIC CABLE IN CONDUIT, 600V (EPRN-TRIPLEXED) 2-1/C NO.6 1-1/C NO.8 GROUND	FOOT	750			750
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	450	450		
X0323080	DRAINAGE SCUPPER, DS-12	EACH	4		4	
X0712400	TEMPORARY PAVEMENT	SQ YD	296	296		
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	162	162		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	18	18		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 50 (CICERO AVENUE) OVER
NORTH BRANCH CHICAGO RIVER

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: AUGUST 18, 2006

DRAWN BY: CLW
CHECKED BY: AAC

