

100% STATE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	57B-3I	COOK	62	6
STA. 20+23.42		TO STA. 28+00.00		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 60440				

SUMMARY OF QUANTITIES			TOTAL QTY.	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT		RDWY 1000-2A	BRIDGE X071-2A	LIGHTING Y030-1E
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	320	320		
X4066602	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	270	270		
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	28	28		
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	667	667		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		
* X8210407	LUMINARE, INSTALL ONLY	EACH	7			7
Z0002600	BAR SPLICERS	EACH	1054		1054	
* Z0008236	DRILLED SHAFT IN SOIL 36"	FT	114		114	
* Z0008242	DRILLED SHAFT IN SOIL 42"	FT	229		229	
* Z0008248	DRILLED SHAFT IN SOIL 48"	FT	114		114	
* Z0008330	DRILLED SHAFT IN ROCK 30"	FT	4		4	
* Z0008336	DRILLED SHAFT IN ROCK 36"	FT	8		8	
* Z0008342	DRILLED SHAFT IN ROCK 42"	FT	4		4	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	14	14		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6		
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	7	7		
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	9	9		
Z0018913	DRILL AND GROUT #8 TIE BARS	EACH	4	4		
Z0039300	PERMANENT CASING	FT	176		176	
△ Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	12	12		
△ Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2		
△ Z0030320	IMPACT ATTENUATORS, RELOCATED (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
X6020270	MANHOLES, TYPE B, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	2	2		
X6040220	FRAMES AND LIDS, TYPE 1, OPEN LID (CITY OF CHICAGO)	EACH	4	4		
* X5615915	DUCTILE IRON PIPE WATERMAIN - 24 INCHES - SUSPENDED	FT	125	125		
* X0324631	REMOVAL OF CONDUIT IN TRENCH	FT	700			700
* X0322124	STORM SEWER (WATERMAIN REQUIREMENTS, 8")	FT	130	130		
* X0322033	STORM SEWER (WATERMAIN REQUIREMENTS, 12")	FT	70	70		
* X0322034	STORM SEWER (WATERMAIN REQUIREMENTS, 15")	FT	100	100		

* SPECIALTY ITEMS
 △ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 ILLINOIS ROUTE 50 (CICERO AVENUE) OVER
 NORTH BRANCH CHICAGO RIVER
 SUMMARY OF QUANTITIES
 SCALE: NONE
 DATE: AUGUST 18, 2006
 DRAWN BY: CLW
 CHECKED BY: AAC

PATRICK
 ENGINEERING INC.
 LISLE, ILLINOIS