

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10.8	10.8			
40600300	AGGREGATE (PRIME COAT)	TON	54	54			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	3	3			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	112	112			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	57	57			
44000103	BITUMINOUS REMOVAL OVER PATCHES 3/4"	SQ YD	1351.5	1351.5			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	541	541			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	406	406			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	406	406			
60603800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-16-12	FOOT	1000	1000			
67000400	ENGINEER'S FIELD OFFICE, (TYPE A)	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	33804	33804			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	92	92			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11268	11268			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1446	1446			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	300	300			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	384	384			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11268	11268			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	482	482			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	128	128			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	720	720			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	720	720			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	598	598			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	2271	2271			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1115	1115			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	27029	27029			
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	397	397			
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2			
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	2	2			
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	132	132			
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	355	355			

9/12/2006
c:\p1\10611801\320288\design\csm\en

* SPECIALTY ITEMS

Rev.11-2-06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS - 1 (HALSTED STREET)
FROM 144th STREET TO 149th STREET
SUMMARY OF QUANTITIES

PLOT DATE: 9/12/2006