F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3730	3268-Z-W-1-RS	COOK	19	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60B35

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10.8	10.8					
40600300	AGGREGATE (PRIME COAT)	TON	54	54					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	112	112					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	57	57					
44000103	BITUMINOUS REMOVAL OVER PATCHES 3/4"	SQ YD	1351.5	1351.5					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	541	541					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	406	406					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	406	406					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	33804	33804					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	92	92					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11268	11268					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1446	1446					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	300	300					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	384	384					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11268	11268					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	482	482					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 1000					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	128	128					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	720	720					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	720	720					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	598	598					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	2271	2271					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1115	1115					
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	27029	27029					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS - 1 (HALSTED STREET)
FROM 144th STREET TO 149th STREET
SUMMARY OF QUANTITIES

PLOT DATE: 9/12/2006

9/12/2006
c:\proj\ects\3322C6\design_ocdgn