


CONTRACT NO. 60889

F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	(537&537 X) T	COOK	8	3
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN 100% STATE Y007
20800150	TRENCH BACKFILL	CU YD	4	4
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	55	55
44000100	PAVEMENT REMOVAL	SQ YD	55	55
55102200	STORM SEWER REMOVAL 66"	FOOT	5	5
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0324078	CONFLICT MANHOLES	EACH	1	1
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	55	55
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	7	7
Z0056800	SANITARY SEWER 6"	FOOT	15	15
67100100	MOBILIZATION	L SUM	1	1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP 351 (US 6 / 159TH STREET) AT METRA ENTRANCE W/O IL 50 SECTION: (537 & 537 X) T SEWER REPAIR
NAME	DATE	
DATE: 9/14/06		DRAWN BY: WS CHECKED BY: PJ
		GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC. CHICAGO, ILLINOIS