F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
541	2000-112 RS	LAKE	35	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 62056

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 100% STATE ROADWAY I000	PARKING LANES 50% STATE 50% CITY Y025	100% CITY Y060
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	39	1	
40600300	AGGREGATE (PRIME COAT)	TON	200	195	5	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	32	31	1	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640		
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	310	310		
42001300	PROTECTIVE COAT	SQ YD	500	500		
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	1000	1000		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1400	1400		
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	1800	1800		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	450	450		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2000	2000		
44003510	MEDIAN REMOVAL (PARTIAL DEPTH)	SQ FT	15000	15000		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1048	1048		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	126	126		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	43	43		
55039700	STORM SEWERS TO BE CLEANED	FOOT	1900	1900		
60249500	VALVE BOXES 8"	EACH	49			49
60250200	CATCH BASINS TO BE ADJUSTED	EACH	30	30		
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	14	14		
60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	16	10		6
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1			1
60260100	INLETS TO BE ADJUSTED	EACH	29	29		
60266910	VALVE BOXES TO BE REMOVED	EACH	49			49
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	183	183		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 100% STATE ROADWAY I000	PARKING LANES 50% STATE 50% CITY Y025	100% CITY Y060
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19500	19500		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	900	900		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	51000	51000		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5000	5000		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	600	600		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1300	1300		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	850	850		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	35100	35100		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	900	900		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	51000	51000		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5000	5000		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	600	600		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1300	1300		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	850	850		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2730	2730		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1917	1917		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2997	2997		

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 9/8/2006

9/8/2006
c:\projects\d1485006\design_aa.dgn