

SUMMARY OF QUANTITIES

100% STATE      100% VILLAGE      95% STATE 5% VILLAGE      100% VILLAGE

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158+thPL.	TRAFFIC SIGNALS US6/94+thAV.	100% STATE INTER CONNECT	100% VILLAGE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL	50% STATE 50% VILLAGE NEW SIDEWALK		
40600990	TEMPORARY RAMP	SQ YD	360	360													
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	1,171	1,171													
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	44,674	44,674													
42001300	PROTECTIVE COAT	SQ YD	10,002	10,002													
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2,622	2,622													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	65,267	39,533													25,734
44000100	PAVEMENT REMOVAL	SQ YD	38,269	38,269													
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	8,406	8,406													
44000300	CURB REMOVAL	FOOT	5,281	5,281													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16,378	16,378													
44000600	SIDEWALK REMOVAL	SQ FT	25,536	25,536													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	837	837													
44003100	MEDIAN REMOVAL	SQ FT	30,556	30,556													
50901105	STEEL RAILING	FOOT	1,242														1,242
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	476	476													
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12	FOOT	2684	2684													
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15	FOOT	1372	1372													
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18	FOOT	830	830													
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21	FOOT	268	268													
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24	FOOT	529	529													
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30	FOOT	936	936													
55100500	STORM SEWER REMOVAL 12"	FOOT	2,313	2,313													
55100700	STORM SEWER REMOVAL 15"	FOOT	970	970													
55100900	STORM SEWER REMOVAL 18"	FOOT	452	452													
55101200	STORM SEWER REMOVAL 24"	FOOT	1,632	1,632													
55101300	STORM SEWER REMOVAL 27"	FOOT	19	19													

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)

SUMMARY OF QUANTITIES

SCALE: N/A      DRAWN BY: BFH  
 DATE: 7-07-06      CHECKED BY: RCH

**McDonough Associates Inc.**  
 Engineers / Architects

Rev. 11-1-06      Rev.

I:\Dgn\sq01002.sht  
 7/31/2006  
 10:53:06 AM