

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
				100% STATE		100% VILLAGE		95% STATE 5% VILLAGE		100% STATE 100% VILLAGE		100% VILLAGE		50% STATE 50% VILLAGE NEW		
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158thPL.	TRAFFIC SIGNALS US6/94thAV.	100% STATE INTER CONNECT	100% VILLAGE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL	SFTY-1B	
* 70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,310	2,310												
* 70400200	RELOCATE ^{TEMPORARY} CONCRETE BARRIER	FOOT	1,790	1,790												
* 72000100	SIGN PANEL - TYPE 1	SQ FT	93		40	38	15									
* 72000200	SIGN PANEL - TYPE 2	SQ FT	120		120											
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	1,128	1,128												
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,006	3,006												
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	19,396	19,396												
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	506	506												
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	34	34												
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	482	482												
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	396	396												
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	92	92												
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	11,890	11,890												
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1									1				
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1									1				
* 80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	36									36				
* 80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	9									9				
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5,236		937	562	209	3,498				30				
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	69		61		8									
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	101		53	20	28									
* 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	13			13										
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30		10	10	10									
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,125		447	137	197	344								
* <u>XX005272</u>	CONDUIT PUSHED, 4" DIA., ^{RIGID} GALVANIZED STEEL	FOOT	4,324		624	491	484					2,725				
* 81400100	HANDHOLE	EACH	18		6	4	3	5								
* 81400200	HEAVY-DUTY HANDHOLE	EACH	9		4	4	1									

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 7-07-06

DRAWN BY: BFH
CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects

Rev. 11-1-06

I:\Dgn\sc01005.sht
7/31/2006
3:20:35 PM