

SUMMARY OF QUANTITIES

100% STATE 100% VILLAGE 95% STATE 5% VILLAGE 100% VILLAGE

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158thPL.	TRAFFIC SIGNALS US6/94thAV.	100% STATE INTER CONNECT	100% VILLAGE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL	50% STATE 50% VILLAGE NEW SIDEWALK		
				J000-2A	Y031-IF	Y031-IF	Y031-IF	Y031-IF	Y031-3D	Y030-1E	Y060	Y060	Y003	Y007	SFT Y-1B		
X0325542	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1,000	1,000													
X0325543	TRANSITION SLEEVE 16"	EACH	1									1					
X0325544	PRESSURE CONNECTION 16" X 8"	EACH	1									1					
X0323828	WATER MAIN TO BE REMOVED 16"	FOOT	1,023									1,023					
X0320772	WATER MAIN TO BE REMOVED 12"	FOOT	132									132					
X0325548	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 26 FT. AND 38 FT.	EACH	1				1										
X0325549	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 32 FT. AND 36 FT.	EACH	1			1											
X0325550	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 36 FT. AND 38 FT.	EACH	1			1											
X0325551	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT AND 22 FT.	EACH	1				1										
X0325552	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT AND 28 FT.	EACH	1				1										
X0325545	PLANTING MIX, FURNISH AND PLACE, 18"	SQ YD	1,072													1,072	
A2002020	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12													12	
A2002218	TREE, ALNUS GLUTINOSA (BLACK ALDER), 2" CALIPER, BALLED AND BURLAPPED	EACH	32													32	
A2004514	TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2-1/2", BALLED AND BURLAPPED	EACH	5													5	
X0800525	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	1									1					
X0800975	TEMPORARY WOOD POLE 100 FT., CLASS 4, 15 FT. MAST ARM	EACH	26									26					
XX005840	FLAGSTONE SIDEWALK (SPECIAL)	SQ FT	2,876													2,876	
X08105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	26									26					
X0325559	LIGHTING CONTROLLER, SPECIAL, 200A, 240/480V	EACH	1									1					
X0325555	ALUMINUM BREAKAWAY, TRANSFORMER BASE	EACH	60									60					
X0325556	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT, TYPE III DISTRIBUTION	EACH	9									9					
X0325557	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT, TYPE IV DISTRIBUTION	EACH	75									75					
X0325558	UNIT DUCT, WITH 5-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	10,650									10,650					
X0325554	MODIFY EXISTING LIGHT POLE, ALUMINUM 47.5 FT. M.H., WITH NEW 15 FT. MAST ARM AND 20A, 120V GFCI RECEPTACLE	EACH	42									42					
X2510630	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	15971													15,971	
X06900530	SOIL DISPOSAL ANALYSIS	EACH	6														
X42400800	DETECTABLE WARNINGS	SQ FT	350													350	
X06900200	NON-SPECIAL WASTE DISPOSAL	CU YD	508													508	
X06900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	11,056													11,056	
X06900450	SPECIAL WASTE PLANS AND REPORTS	L SUM															
X06901000	BACKFILL PLUGS	CU YD	43													43	
X0301828	ENGINEERED BARRIER	SQ YD	1,546													1,546	

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)

SUMMARY OF QUANTITIES

SCALE: N/A DRAWN BY: BFH
DATE: 7-07-06 CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects

Rev. 11-1-06
Rev. 9-11-06

I:\Dgn\so01011.sht
 7/31/2006
 11:57:46 AM